

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Balasore	<b>Block</b>	Bahanaga	<b>Gram Panchayat</b>	Latharpentha

<b>Work Code</b>	OD/346/3298/116059/393817/00064366 (REPAIR AND RESTORATION OF ROAD FROM RD ROAD TO MAHENDRA MALIK HOUSE)						
<b>Project Category</b>	Road						

<b>Financial Year</b>	2024-25	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Bahanaga	<b>Proposal Date</b>	13-07-2018
<b>Date of Commencement</b>	-	<b>Date of Completion</b>	
<b>Scheme Name</b>	Severe Cyclonic Storm DANA 2024	<b>Scheme Component Name</b>	Self/Personal Deposit
<b>Project Sub-Category</b>	CC Road	<b>Project Type</b>	Repair and Maintenance
<b>Name of Executant</b>			

### Administrative Approval Details

<b>Approval No.</b>	
---------------------	--

### Technical Sanction Details

<b>Technical Sanction No.</b>	
<b>Fund Sanction No.</b>	30774
<b>Fund Sanction Amount (in Rs.)</b>	60000

### ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;"><b>Earth Work (AR0102aa)</b>  <b>: Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b>  Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	0.7645536	240.77592	184.08609642931
2	<p style="text-align: center;"><b>Earth Work (AR0115) :</b>  <b>Filling foundation and plinth with sand well watered and rammed -</b>  Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	3.104087616	1316.033232	4085.0824576957

3	<p style="text-align: center;"><b>Concrete (AR0303) :</b>  <b>Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b> - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	4.12858944	6149.5374292	25388.91529108
4	<p style="text-align: center;"><b>R.C.C. Work (AR0410c) :</b>  <b>R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc</b> - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	Sqm	11.0368764	216.39264180804	2388.2988415048

5	<p><b>Concrete (AR0307a) : Cement concrete (1:2:4)with 12mm size hard granite(Hand broken)chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(hand broken) chips including hoisting and laying in position compacting to proper thickness and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</b></p>	Cum	3.36403584	7272.6013944	24465.291740796
<b>Total Amount (in Rs.): 56511.674427505</b>					

## LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Meaurement Qty)	Unit
1	<p><b>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b> Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	0.7645536	Cum

	i	Un-Skilled	0.516	0.3945096576	-
2		<b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed</b> - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	3.104087616	Cum
	i	Un-Skilled	0.1236	0.3836652293376	-
3		<b>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b> - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	4.12858944	Cum
	i	Skilled	0.18	0.7431460992	-
	ii	Un-Skilled	3.9	16.101498816	-

4	<p><b>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	11.0368764	Sqm
i	Semi-Skilled	0.05	0.55184382	-
ii	Skilled	0.05	0.55184382	-
5	<p><b>Concrete (AR0307a) : Cement concrete (1:2:4)with 12mm size hard granite(Hand broken)chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(hand broken) chips including hoisting and laying in position compacting to proper thickness and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	3.36403584	Cum
i	Un-Skilled	4.6	15.474564864	-
ii	Skilled	0.68	2.2875443712	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	32.354238566938	462	14947.658217925
2	Skilled	3.5825342904	562	2013.3842712048
3	Semi-Skilled	0.55184382	512	282.54403584
<b>Total:</b>				<b>17243.58652497</b>

## MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	<b>0.7645536</b>	Cum
2	<b>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	<b>3.104087616</b>	Cum
i)	<b>BRM029</b> : Sand for filling and road blinding	1	3.104087616	1 Cum

3	<p><b>Concrete (AR0303)</b>  <b>:.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	<b>4.12858944</b>	Cum
i)	<b>BRM340</b> : Cement	2.29	9.4544698176	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	1.9817229312	1 Cum
iii)	<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	3.9634458624	1 Cum.
4	<p><b>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b>  Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	<b>11.0368764</b>	Sqm
i)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.029468459988	1Cum.
ii)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.126	1.3906464264	1Mtr.

5	<b>Concrete (AR0307a)</b> :.Cement concrete (1:2:4)with 12mm size hard granite(Hand broken)chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(hand broken) chips including hoisting and laying in position compacting to proper thickness and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.	-	3.36403584	Cum
i)	<b>BRM057</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.9	3.027632256	1 Cum.
ii)	<b>BRM340</b> : Cement	3.23	10.8658357632	1 Qntl.
iii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1.513816128	1 Cum

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM029</b>	3.104087616	1 Cum	803.65	2494.6000125984
2	<b>BRM340</b>	20.3203055808	1 Qntl.	567.932	11540.551789115
3	<b>BRM028</b>	3.4955390592	1 Cum	808.59	2826.4579278785
4	<b>BRM044</b>	3.9634458624	1 Cum.	1596.76	6328.6718152458
5	<b>BRM104</b>	0.029468459988	1Cum.	58620.646	1727.4601611217
6	<b>BRM092</b>	1.3906464264	1Mtr.	276.666	384.74458420638
7	<b>BRM057</b>	3.027632256	1 Cum.	1651.51	5000.1649471066
<b>Total: 30302.651237272</b>					

## ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM029</b>	3.104087616	1 Cum	442.25	1372.782748176
2	<b>BRM028</b>	3.4955390592	1 Cum	442.25	1545.9021489312
3	<b>BRM044</b>	3.9634458624	1 Cum.	552.5	2189.803838976

4	BRM057	3.027632256	1 Cum.	552.5	1672.76682144
					<b>Total: 6781.2555575232</b>

#### ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ 1%	Rs. 565.11674427505
2	Display Citizen Board @ Rs. 1500	Rs. 1500
3	Any Other Lumpsum @ Rs. 1423.2	Rs. 1423.2
		<b>Total Addition Component Amount (in Rs.): 3488.3167442751</b>

**Total Net Amount (in Rs.): 59999.99117178**