

ESTIMATION DPR							
State	Odisha	District	Nabarangpur	Block	Jhorigam	Gram Panchayat	Ichhapur

Work Code	OD/366/3515/275423/427528/00065610 (Construction of VSS Building Kadamali of Ichhapur GP)						
Project Category	Building						

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Jhorigam	Proposal Date	01-08-2024
Date of Commencement	-	Date of Completion	
Scheme Name	Construction of Vana Suraksha Samiti Building	Scheme Component Name	Construction of Buildings for Vana Suraksha Samiti
Project Sub-Category	Vana Suraksha Samiti Building	Project Type	New Work
Name of Executant			

Administrative Approval Details

Approval No.	
--------------	--

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	18481
Fund Sanction Amount (in Rs.)	850000

ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;">Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	33.3327	240.77592	8025.711508584
2	<p style="text-align: center;">Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	24.6356	693.034932	17073.331370779

3	<p style="text-align: center;">Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	17.03245	5438.0287993	92622.953622637
4	<p style="text-align: center;">Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifcaion and direction of Engineer-in charge.</p>	Cum	1.50875	6957.8658711	10497.680133022

5	<p style="text-align: center;">R.C.C. Work (AR0404A) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips -</p> <p>Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)</p>	Cum	15.561587	5622.216871681	87490.616981532
---	---	-----	-----------	----------------	-----------------

6	<p style="text-align: center;">R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in- charge.</p>	Qntl	15.5	8430.7391448	130676.4567444
7	<p style="text-align: center;">R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	Sqm	61.0908	216.55039071844	13229.236609302

8	<p style="text-align: center;">R.C.C. Work (AR0410e) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm</p>	Sqm	10.302	500.00130144795	5151.0134075168
9	<p style="text-align: center;">R.C.C. Work (AR0410b) : centering and shuttering fRigid and smooth or R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. stairs excluding landing but including railing details for 5 Sqm</p>	Sqm	8.6625	919.009696506	7960.9214959832

10	<p style="text-align: center;">R.C.C. Work (AR0410d) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, girder and bressmer, etc. Data for 4.2sqm</p>	Sqm	36.5884	1048.4253517895	38360.206141415
11	<p style="text-align: center;">R.C.C. Work (AR0410a) : Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height</p>	Sqm	51.2174	663.90898015022	34003.691799946

12	<p style="text-align: center;">Masonry</p> <p>Brick Work (AR0603di) : C.B. Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:4) in superstructure - Brickwork with C.B. Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	Cum	24.834825	4991.394043	123960.39756395
13	<p>Plastering (AR1004) : 12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.</p>	Sqm	102.3433	170.317128806	17430.817008531

14	<p>Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	Sqm	112.29	244.66334031	27473.24648341
15	<p>Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	Sqm	35.425	1009.880238341	35775.00744323

16	<p style="text-align: center;">Painting (AR0918c) : Finishing wall with two coat water proofing cement paint including one coat cement wash on the outer surface of approved shade on new work (Outside) - Finishing wall with two coat water proofing cement paint including one coat cement wash on the outer surface of approved shade on new work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in- charge. (Outside)</p>	Sqm	85.6125	57.890317259086	4956.1347863435
17	<p style="text-align: center;">Other Building Items. (AR1902) : cement based wall putty (water based) - Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,e tc.complete. and as per the direction of Engineer in Charge.</p>	Sqm	147.715	79.21834	11701.7370931

18	<p style="text-align: center;">Painting (AR0920) : Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p>	Sqm	147.715	94.7676397125	13998.601900132
19	<p style="text-align: center;">Iron Work (AR1704) : Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.</p>	Qntl	3.2655	15773.439083087	51508.165325821

20	<p align="center">Painting (AR0901b) : Priming one coat in inner surface with primer of approved quality over iron work. - Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.</p>	Sqm	23.8725	65.84406247451	1571.8623814227
21	<p align="center">Other Building Items. (AR1911) : Stainless steel of 304 grade in hand railing using 50mm dia of 2mm - Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete in all respect. and as per direction of Engineer in Charge</p>	Rmt	8.25	3129.0244276074	25814.451527761
Total Amount (in Rs.): 759282.24132882					

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift -</p> <p>Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	33.3327	Cum
i	Un-Skilled	0.516	17.1996732	-
2	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed -</p> <p>Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	24.6356	Cum
i	Un-Skilled	0.1236	3.04496016	-

3	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	17.03245	Cum
i	Skilled	0.18	3.065841	-
ii	Un-Skilled	3.9	66.426555	-
4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	1.50875	Cum
i	Un-Skilled	4.6	6.94025	-

	ii	Skilled	0.68	1.02595	-
5		R.C.C. Work (AR0404A) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	15.561587	Cum
	i	Un-Skilled	1.3333	20.7482639471	-
	ii	Skilled	0.1	1.5561587	-
	iii	Semi-Skilled	0.0573	0.8916789351	-

6	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	15.5	Qntl
i	Un-Skilled	0.8	12.4	-
ii	Highly-Skilled	0.3	4.65	-
iii	Semi-Skilled	0.044	0.682	-
7	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	61.0908	Sqm
i	Semi-Skilled	0.05	3.05454	-

	ii	Skilled	0.05	3.05454	-
8		R.C.C. Work (AR0410e) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm	-	10.302	Sqm
	i	Semi-Skilled	0.16025641025641	1.6509615384615	-
	ii	Skilled	0.16025641025641	1.6509615384615	-
9		R.C.C. Work (AR0410b) : centering and shuttering fRigid and smooth or R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. stairs excluding landing but including railing details for 5 Sqm	-	8.6625	Sqm
	i	Semi-Skilled	0.55	4.764375	-
	ii	Skilled	0.55	4.764375	-

10	R.C.C. Work (AR0410d) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm	-	36.5884	Sqm
i	Semi-Skilled	0.6547619047619	23.95669047619	-
ii	Skilled	0.6547619047619	23.95669047619	-
11	R.C.C. Work (AR0410a) : Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height	-	51.2174	Sqm
i	Semi-Skilled	0.305555555555556	15.6497611111111	-
ii	Skilled	0.305555555555556	15.6497611111111	-

12	<p>Masonry Brick Work (AR0603di) : C.B. Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:4) in superstructure - Brickwork with C.B. Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	24.834825	Cum
	i Un-Skilled	2.96	73.511082	-
	ii Skilled	1.05	26.07656625	-
	iii Highly-Skilled	0.35	8.69218875	-
13	<p>Plastering (AR1004) : 12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.</p>	-	102.3433	Sqm
	i Un-Skilled	0.12	12.281196	-

	ii	Skilled	0.14	14.328062	-
14		Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	112.29	Sqm
	i	Un-Skilled	0.24	26.9496	-
	ii	Skilled	0.16	17.9664	-
15		Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in- charge(for new work only)	-	35.425	Sqm
	i	Un-Skilled	0.216	7.6518	-

	ii	Highly-Skilled	0.216	7.6518	-
16		<p>Painting (AR0918c) : Finishing wall with two coat water proofing cement paint including one coat cement wash on the outer surface of approved shade on new work (Outside) - Finishing wall with two coat water proofing cement paint including one coat cement wash on the outer surface of approved shade on new work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)</p>	-	85.6125	Sqm
	i	Un-Skilled	0.042752688172043	3.660164516129	-
	ii	Highly-Skilled	0.022	1.883475	-
	iii	Skilled	0.0080645161290323	0.69042338709677	-
17		<p>Other Building Items. (AR1902) : cement based wall putty (water based) - Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc. complete. and as per the direction of Engineer in Charge.</p>	-	147.715	Sqm

	i	Un-Skilled	0.057	8.419755	-
	ii	Skilled	0.05	7.38575	-
18		Painting (AR0920) : Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	147.715	Sqm
	i	Highly-Skilled	0.054	7.97661	-
	ii	Un-Skilled	0.064	9.45376	-
19		Iron Work (AR1704) : Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	3.2655	Qntl
	i	Un-Skilled	6.3976377952756	20.891486220472	-
	ii	Semi-Skilled	1.9685039370079	6.4281496062992	-

	iii	Skilled	3.9370078740157	12.856299212598	-
	iv	Highly-Skilled	3.4448818897638	11.249261811024	-
20		Painting (AR0901b) : Priming one coat in inner surface with primer of approved quality over iron work. - Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	23.8725	Sqm
	i	Highly-Skilled	0.053763440860215	1.2834677419355	-
	ii	Un-Skilled	0.053763440860215	1.2834677419355	-

21	<p>Other Building Items. (AR1911) : Stainless steel of 304 grade in hand railing using 50mm dia of 2mm - Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete in all respect. and as per direction of Engineer in Charge</p>	-	8.25	Rmt	
	i	Semi-Skilled	0.27300613496933	2.2523006134969	-
	ii	Highly-Skilled	0.27300613496933	2.2523006134969	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	290.86201378564	462	134378.25036896
2	Skilled	134.02777867546	562	75323.611615608
3	Semi-Skilled	59.330457280659	512	30377.194127698
4	Highly-Skilled	45.639103916456	612	27931.131596871
Total: 268010.18770914				

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
--------	------------------------	---	---------------------------	------

1	<p>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	33.3327	Cum
2	<p>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	24.6356	Cum
i)	BRM029 : Sand for filling and road blinding	1	24.6356	1 Cum
3	<p>Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	17.03245	Cum
i)	BRM340 : Cement	2.29	39.0043105	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	8.175576	1 Cum

iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	16.351152	1 Cum.
4	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	1.50875	Cum
i)	BRM340 : Cement	3.23	4.8732625	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.6789375	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1.357875	1 Cum.

5	R.C.C. Work (AR0404A) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	15.561587	Cum
i)	BRM340 : Cement	3.4733	54.0500601271	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	7.00271415	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	5.60217132	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	8.40325698	1 Cum.

6	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	15.5	Qntl
i)	BRM162 : Binding Wire.	0.8	12.4	1 Kg.
ii)	BRM341 : Steel	1.05	16.275	1 Qntl.
7	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	61.0908	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.163112436	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	7.6974408	1Mtr.

8	R.C.C. Work (AR0410e) :.Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm	-	10.302	Sqm
i)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.26923076923077	2.7736153846154	1Mtr.
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0052948717948718	0.054547769230769	1Cum.
9	R.C.C. Work (AR0410b) :.centering and shuttering fRigid and smooth or R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. stairs excluding landing but including railing details for 5 Sqm	-	8.6625	Sqm
i)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.13	1.126125	1Mtr.
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00534	0.04625775	1Cum.

10	R.C.C. Work (AR0410d) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, girder and bressmer, etc. Data for 4.2sqm	-	36.5884	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.55238095238095	20.210735238095	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0051904761904762	0.18991121904762	1Cum.
11	R.C.C. Work (AR0410a) : Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas - Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height	-	51.2174	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.622222222222222	31.8686044444444	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0050222222222222	0.257225164444444	1Cum.

12	<p>Masonry Brick Work (AR0603di) :C.B. Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:4) in superstructure - Brickwork with C.B. Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	24.834825	Cum
i)	<p>BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK</p>	1	24.834825	1 Cum
ii)	<p>BRM001 : Well burnt clamp burnt bricks (25 Cm. x 12Cm. x 8Cm.) having crushing strength not less than 35 Kg./Cm² with dimensional tolerance ± 8 percent.</p>	350	8692.18875	1000 Nos
iii)	<p>BRM340 : Cement</p>	1	24.834825	1 Qntl.
iv)	<p>BRM028 : Screened and washed sharp sand for mortar</p>	0.28	6.953751	1 Cum
13	<p>Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.</p>	-	102.3433	Sqm
i)	<p>BRM340 : Cement</p>	0.0358	3.66389014	1 Qntl.

ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.5351495	1 Cum
14	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	112.29	Sqm
i)	BRM340 : Cement	0.043	4.82847	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	2.02122	1 Cum
15	Other Building Items. (AR1901B) :.Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)	-	35.425	Sqm
i)	BRM174 : White Cement.	0.0076	0.26923	1Qntl
ii)	BRM340 : Cement	0.1074	3.804645	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.021	0.743925	1 Cum

iv)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B Ia) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	35.425	1 Sqm.
16	Painting(AR0918c) :.Finishing wall with two coat water proofing cement paint including one coat cement wash on the outer surface of approved shade on new work (Outside) - Finishing wall with two coat water proofing cement paint including one coat cement wash on the outer surface of approved shade on new work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)	-	85.6125	Sqm
i)	BRM143 : Cement paint	0.25	21.403125	1 Kg.
ii)	BRM340 : Cement	0.010763440860215	0.92148508064516	1 Qntl.
17	Other Building Items. (AR1902) :.cement based wall putty (water based) - Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc. complete. and as per the direction of Engineer in Charge.	-	147.715	Sqm
i)	BRMMR0038 : Cement based putty	0.8	118.172	kg

18	Painting(AR0920) :.Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	147.715	Sqm
i)	BRM140 : Plastic Emulsion paint	0.125	18.464375	1 Litre
19	Iron Work(AR1704) :.Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	3.2655	Qntl
i)	BRM341 : Steel	1	3.2655	1 Qntl.
20	Painting(AR0901b) :.Priming one coat in inner surface with primer of approved quality over iron work. - Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	23.8725	Sqm
i)	BRM137 : Red oxide Primer	0.054	1.289115	1 Litre

21	Other Building Items. (AR1911) :.Stainless steel of 304 grade in hand railing using 50mm dia of 2mm - Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost,conveyance, taxes of all materials, labour,T&P etc. required for the complete in all respect. and as per direction of Engineer in Charge	-	8.25	Rmt
i)	BRMMR0024 : Buffing, Polishing etc.	0.30674846625767	2.5306748466258	L.S.
ii)	BRMMR0023 : Fabrication	10.478527607362	86.447852760736	kg
iii)	BRMMR0022 : Stainless steel square pipe bracing of size 32mmx32mmx2mm in 3 rows	5.101226993865	42.085122699387	kg
iv)	BRMMR0021 : Balustrade of size 30mmx32mmx2mm	1.8773006134969	15.48773006135	kg
v)	BRMMR0020 : Railing 50mm outer dia of 2mm thick	3.5	28.875	kg

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	24.6356	1 Cum	478.15	11779.51214
2	BRM340	135.98094834775	1 Qntl.	597.677	81272.685265635
3	BRM028	27.11127315	1 Cum	482.34	13076.851491171
4	BRM044	16.351152	1 Cum.	1466.56	23979.94547712
5	BRM056	1.357875	1 Cum.	1867.93	2536.41544875
6	BRM060	5.60217132	1 Cum.	1824.88	10223.290398442
7	BRM052	8.40325698	1 Cum.	1788.5	15029.22510873
8	BRM162	12.4	1 Kg.	90.1	1117.24
9	BRM341	19.5405	1 Qntl.	6219.847	121538.9203035

10	BRM104	0.71105433872283	1Cum.	58668.206	41716.282421385
11	BRM092	7.6974408	1Mtr.	324.226	2495.7104408208
12	BRM094	3.8997403846154	1Mtr.	335.226	1307.2943701731
13	BRM084	52.07933968254	1Mtr	345.286	17982.266881625
14	BRMMR0025	24.834825	1 Cum	33	819.549225
15	BRM001	8692.18875	1000 Nos	5.24242	45568.104146775
16	BRM174	0.26923	1Qntl	2053.857	552.95992011
17	BRM131	35.425	1 Sqm.	663.9538891	23520.566521368
18	BRM143	21.403125	1 Kg.	48.19677	1031.5614929062
19	BRMMR0038	118.172	kg	30	3545.16
20	BRM140	18.464375	1 Litre	249.70677	4610.6794413187
21	BRM137	1.289115	1 Litre	137.96677	177.85503270855
22	BRMMR0024	2.5306748466258	L.S.	178.42	451.52300613497
23	BRMMR0023	86.447852760736	kg	10	864.47852760736
24	BRMMR0022	42.085122699387	kg	256.62	10799.884187117
25	BRMMR0021	15.48773006135	kg	256.62	3974.4612883436
26	BRMMR0020	28.875	kg	240.24	6936.93
Total: 446909.35253674					

ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	24.6356	1 Cum	150.92	3718.004752
2	BRM028	27.11127315	1 Cum	150.92	4091.633343798
3	BRM044	16.351152	1 Cum.	176.5	2885.978328
4	BRM056	1.357875	1 Cum.	176.5	239.6649375
5	BRM060	5.60217132	1 Cum.	176.5	988.78323798
6	BRM052	8.40325698	1 Cum.	176.5	1483.17485697
7	BRM001	8692.18875	1000 Nos	0.07525	654.0872034375
Total: 14061.326659685					

ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Provision for PH Work @ Rs. 30000	Rs. 30000
2	Provision for EI Work @ Rs. 30000	Rs. 30000

3	Provision for Contingency @ Rs. 8500	Rs. 8500
4	Display Citizen Board @ Rs. 4500	Rs. 4500
5	Any Other Lumpsum @ Rs. 17717	Rs. 17717
Total Addition Component Amount (in Rs.): 90717		

Total Net Amount (in Rs.): 849999.24132882