

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Jajpur	<b>Block</b>	Dharmasala	<b>Gram Panchayat</b>	Sahanidiha

<b>Work Code</b>	OD/356/3397/118359/401400/00070474 (Construction Of Concrete Road From Lunibara Laxmidhara Pradhan House To Pond)						
<b>Project Category</b>	Road						

<b>Financial Year</b>	2025-26	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Dharmasala	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	-	<b>Date of Completion</b>	
<b>Scheme Name</b>	Bikashita Gaon Bikashita Odisha	<b>Scheme Component Name</b>	Viksit Gaon Vikshit Odisha (VGVO)
<b>Project Sub-Category</b>	CC Road	<b>Project Type</b>	New Work
<b>Name of Executant</b>			

### Administrative Approval Details

<b>Approval No.</b>	
---------------------	--

### Technical Sanction Details

<b>Technical Sanction No.</b>	
<b>Fund Sanction No.</b>	3645
<b>Fund Sanction Amount (in Rs.)</b>	450000

### ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;"><b>Earth Work (AR0102aa)</b>  <b>: Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b>  Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	7.05	240.77592	1697.470236
2	<p style="text-align: center;"><b>Earth Work (AR0115) :</b>  <b>Filling foundation and plinth with sand well watered and rammed -</b>  Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	25.85	787.298232	20351.6592972

3	<p style="text-align: center;"><b>Concrete (AR0303) :</b>  <b>Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b> - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	37.6	5546.69135216	208555.59484122
4	<p style="text-align: center;"><b>Concrete (AR0307) :</b>  <b>Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum</b> - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifcaion and direction of Engineer-in charge.</p>	Cum	28.2	7071.52064792	199416.88227134

5	<b>R.C.C. Work (AR0410c) :</b> <b>R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc</b> - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	Sqm	56.4	216.23489289764	12195.647959427
<b>Total Amount (in Rs.): 442217.25460519</b>					

#### LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<b>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b> - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	7.05	Cum
i	Un-Skilled	0.516	3.6378	-

2	<p><b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	25.85	Cum
i	Un-Skilled	0.1236	3.19506	-
3	<p><b>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	37.6	Cum
i	Skilled	0.18	6.768	-
ii	Un-Skilled	3.9	146.64	-

4	<p><b>Concrete (AR0307) :</b>  <b>Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b>  Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	28.2	Cum
i	Un-Skilled	4.6	129.72	-
ii	Skilled	0.68	19.176	-
5	<p><b>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b>  Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	56.4	Sqm
i	Semi-Skilled	0.05	2.82	-
ii	Skilled	0.05	2.82	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	283.19286	462	130835.10132
2	Skilled	28.764	562	16165.368
3	Semi-Skilled	2.82	512	1443.84
				<b>Total: 148444.30932</b>

## MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	<b>7.05</b>	Cum
2	<b>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	<b>25.85</b>	Cum
i)	<b>BRM029</b> : Sand for filling and road blinding	1	25.85	1 Cum

3	<p><b>Concrete (AR0303)</b>  <b>:.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	37.6	Cum
i)	<b>BRM340</b> : Cement	2.29	86.104	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	18.048	1 Cum
iii)	<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	36.096	1 Cum.
4	<p><b>Concrete (AR0307)</b>  <b>:.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b>  Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	28.2	Cum
i)	<b>BRM340</b> : Cement	3.23	91.086	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	12.69	1 Cum

iii)	<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	25.38	1 Cum.
5	<b>R.C.C. Work (AR0410c) :-R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	56.4	Sqm
i)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.150588	1Cum.
ii)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.126	7.1064	1Mtr.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM029</b>	25.85	1 Cum	413.05	10677.3425
2	<b>BRM340</b>	177.19	1 Qntl.	574.612	101815.50028
3	<b>BRM028</b>	30.738	1 Cum	417.99	12848.17662
4	<b>BRM044</b>	36.096	1 Cum.	1281.71	46264.60416
5	<b>BRM056</b>	25.38	1 Cum.	1727.51	43844.2038
6	<b>BRM104</b>	0.150588	1Cum.	58573.086	8820.403874568
7	<b>BRM092</b>	7.1064	1Mtr.	229.106	1628.1188784
<b>Total: 225898.35011297</b>					

## ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM029</b>	25.85	1 Cum	309.35	7996.6975
2	<b>BRM028</b>	30.738	1 Cum	309.35	9508.8003
3	<b>BRM044</b>	36.096	1 Cum.	488.75	17641.92

4	BRM056	25.38	1 Cum.	488.75	12404.475
					<b>Total: 47551.8928</b>

**ADDITION COMPONENT**

SI.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ Rs. 4500	Rs. 4500
2	Display Citizen Board @ Rs. 3282	Rs. 3282
		<b>Total Addition Component Amount (in Rs.): 7782</b>

**Total Net Amount (in Rs.): 449999.25460519**