

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Jajpur	<b>Block</b>	Sukinda	<b>Gram Panchayat</b>	Lambo

<b>Work Code</b>	OD/356/3403/118505/400408/00064469 (CONST. OF BUS STAND SHED AT LEMBO)
<b>Project Category</b>	Other Infrastructure

<b>Financial Year</b>	2023-24	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Sukinda	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	-	<b>Date of Completion</b>	
<b>Scheme Name</b>	SFC Devolution of Fund	<b>Scheme Component Name</b>	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
<b>Project Sub-Category</b>	Waiting Hall	<b>Project Type</b>	New Work
<b>Name of Executant</b>			

### Administrative Approval Details

<b>Approval No.</b>	
---------------------	--

### Technical Sanction Details

<b>Technical Sanction No.</b>	
<b>Fund Sanction No.</b>	
<b>Fund Sanction Amount (in Rs.)</b>	400000

### ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;"><b>Earth Work (AR0102aa)</b>  <b>: Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b>  Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	15.721376	240.77592	3785.3287700659
2	<p style="text-align: center;"><b>Earth Work (AR0115) :</b>  <b>Filling foundation and plinth with sand well watered and rammed -</b>  Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	14.034896	1172.653632	16458.071769142

3	<p style="text-align: center;"><b>Concrete (AR0303) :</b>  <b>Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	3.28112	6175.10251486	20261.252363557
---	---	-----	---------	---------------	-----------------

4	<p style="text-align: center;"><b>Masonry</b></p> <p><b>Brick Work (AR0603b) :</b>  <b>Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth -</b> Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&amp;P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	Cum	6.72635	5105.018684248	34338.142426792
---	---	-----	---------	----------------	-----------------

5	<p style="text-align: center;"><b>Masonry</b></p> <p><b>Brick Work (AR0603bi) :</b>  <b>Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure -</b>  Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance <math>\pm 8</math> percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&amp;P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	Cum	8.865775	5138.348684248	45555.443306089
---	---	-----	----------	----------------	-----------------

6	<p style="text-align: center;"><b>R.C.C. Work (AR0404Aa) :</b></p> <p><b>Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b> Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&amp;P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concreate, pre-cast slabs etc.)</p>	Cum	0.0397709456	6721.4890554143	267.31997557388
---	---	-----	--------------	-----------------	-----------------

7	<p style="text-align: center;"><b>R.C.C. Work (AR0404Ab) :</b></p> <p><b>Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b> Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&amp;P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)</p>	Cum	1.14125	7478.8633017424	8535.2527431135
---	--	-----	---------	-----------------	-----------------

8	<p style="text-align: center;"><b>R.C.C. Work (AR0404Ac) :</b></p> <p><b>Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b> Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&amp;P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder &amp; Bressmer etc)</p>	Cum	2.712875	14781.178575869	40099.489829011
---	--	-----	----------	-----------------	-----------------

9	<p style="text-align: center;"><b>R.C.C. Work (AR0404Ag) :</b></p> <p><b>Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b> Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&amp;P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)</p>	Cum	3.479592	13029.231410832	45336.40938328
---	---	-----	----------	-----------------	----------------

10	<p><b>Plastering (AR1027) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) -</b>  6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T &amp; P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p>	Sqm	17.3455	192.7722385048	3343.730862985
11	<p><b>Plastering (AR1004) : 12mm thick cement plaster (1:6) over Brick work in inside -</b>  12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc. comp.and as per direction of Engineer-in-charge.</p>	Sqm	36.7956	176.8783060772	6508.3433990942

12	<p><b>Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. -</b>  16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	Sqm	24.4496	252.536032962	6174.4049915077
13	<p><b>Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory -</b>  Supplying, fitting &amp; fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&amp;P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	Sqm	16.2936	1018.6282783586	16597.121716264

14	<p style="text-align: center;"><b>Flooring (AR0817aa) :</b>  <b>Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) -</b>  Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	Sqm	17.7328	1536.741499572	27250.72966361
----	--	-----	---------	----------------	----------------

15	<p style="text-align: center;"><b>Flooring (AR0816j) : Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 -</b> Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the Chequered tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	Sqm	7.3744	957.8269769958	7063.3992591578
16	<p style="text-align: center;"><b>Painting (AR0901d) :</b> <b>Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) -</b> Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&amp;P required for the work complete as per direction of the Engineer-in- charge.</p>	Sqm	31.8364	71.55359310071	2278.0088113914

17	<p style="text-align: center;"><b>Painting (AR0920) :</b>  <b>Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) -</b>          Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p>	Sqm	31.8364	94.7706419375	3017.156064979
18	<p style="text-align: center;"><b>Painting (AR0918cb) :</b>  <b>Finishing wall two coats with weather coat with one coat waterbound Primer -</b> Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)</p>	Sqm	42.7246	160.20743549879	6844.7985987116

19	<p style="text-align: center;"><b>Other Building Items. (AR1911) :</b></p> <p><b>Stainless steel of 304 grade in hand railing using 50mm dia of 2mm</b></p> <p>- Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&amp;P etc. required for the complete in all respect. and as per direction of Engineer in Charge</p>	Rmt	6.34	3129.0244276074	19838.014871031
----	--	-----	------	-----------------	-----------------

20	<p><b>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position -</b>  Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	Qntl	9	8444.999052	76004.991468
<b>Total Amount (in Rs.): 389557.41027336</b>					

## LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<p><b>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b>  Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	15.721376	Cum

	i	Un-Skilled	0.516	8.112230016	-
2		<b>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	14.034896	Cum
	i	Un-Skilled	0.1236	1.7347131456	-
3		<b>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal -</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	3.28112	Cum
	i	Skilled	0.18	0.5906016	-
	ii	Un-Skilled	3.9	12.796368	-

4	<b>Masonry Brick Work (AR0603b) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth</b> - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm <sup>2</sup> with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	6.72635	Cum
i	Un-Skilled	2.96	19.909996	-
ii	Skilled	1.05	7.0626675	-
iii	Highly-Skilled	0.35	2.3542225	-

5	<b>Masonry Brick Work (AR0603bi) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure -</b> Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm <sup>2</sup> with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	8.865775	Cum
i	Un-Skilled	2.96	26.242694	-
ii	Skilled	1.05	9.30906375	-
iii	Highly-Skilled	0.35	3.10302125	-

6	<b>R.C.C. Work (AR0404Aa) :</b> <b>Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)	-	0.0397709456	Cum
i	Un-Skilled	1.3333	0.05302660176848	-
ii	Skilled	0.175	0.00695991548	-
iii	Semi-Skilled	0.1323	0.00526169610288	-

7	<b>R.C.C. Work (AR0404Ab) : Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	1.14125	Cum
i	Un-Skilled	1.3333	1.521628625	-
ii	Skilled	0.35	0.3994375	-
iii	Semi-Skilled	0.3073	0.350706125	-

8	<b>R.C.C. Work (AR0404Ac) :</b> <b>Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	2.712875	Cum
i	Un-Skilled	1.3333	3.6170762375	-
ii	Skilled	5.33875	14.48336140625	-
iii	Semi-Skilled	5.29605	14.36752164375	-

9	<b>R.C.C. Work (AR0404Ag) :</b> <b>Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	3.479592	Cum
i	Un-Skilled	1.3333	4.6393400136	-
ii	Skilled	3.15525	10.978982658	-
iii	Semi-Skilled	3.11255	10.8304040796	-

10	<p><b>Plastering (AR1027) :</b>  <b>6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) -</b> 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T &amp; P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p>	-	17.3455	Sqm
i	Un-Skilled	0.17	2.948735	-
ii	Skilled	0.14	2.42837	-
11	<p><b>Plastering (AR1004) :</b>  <b>12mm thick cement plaster (1:6) over Brick work in inside -</b> 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc. comp.and as per direction of Engineer-in-charge.</p>	-	36.7956	Sqm
i	Un-Skilled	0.12	4.415472	-
ii	Skilled	0.14	5.151384	-

12	<p><b>Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside.</b> - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T &amp; P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	-	24.4496	Sqm
i	Un-Skilled	0.24	5.867904	-
ii	Skilled	0.16	3.911936	-
13	<p><b>Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory</b> - Supplying, fitting &amp; fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&amp;P , etc. required for the work all complete as per direction of Engineer-in- charge(for new work only)</p>	-	16.2936	Sqm
i	Un-Skilled	0.216	3.5194176	-
ii	Highly-Skilled	0.216	3.5194176	-

14	<p><b>Flooring (AR0817aa)</b>  <b>: Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) -</b>          Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	17.7328	Sqm
i	Highly-Skilled	0.325	5.76316	-
ii	Un-Skilled	0.325	5.76316	-
iii	Semi-Skilled	0.76	13.476928	-

15	<p><b>Flooring (AR0816j) : Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 -</b>  Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the Chequered tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	7.3744	Sqm
	i Un-Skilled	0.216	1.5928704	-
	ii Highly-Skilled	0.216	1.5928704	-
	iii Semi-Skilled	0.55	4.05592	-
16	<p><b>Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) -</b> Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&amp;P required for the work complete as per direction of the Engineer-in-charge.</p>	-	31.8364	Sqm
	i Highly-Skilled	0.053763440860215	1.7116344086022	-

	ii	Un-Skilled	0.053763440860215	1.7116344086022	-
17		<b>Painting (AR0920) : Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) -</b> Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	31.8364	Sqm
	i	Highly-Skilled	0.054	1.7191656	-
	ii	Un-Skilled	0.064	2.0375296	-
18		<b>Painting (AR0918cb) : Finishing wall two coats with weather coat with one coat waterbound Primer -</b> Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	42.7246	Sqm
	i	Un-Skilled	0.11776344086022	5.0313959053763	-
	ii	Highly-Skilled	0.10776344086022	4.6041499053763	-

19	<p><b>Other Building Items. (AR1911) : Stainless steel of 304 grade in hand railing using 50mm dia of 2mm</b> - Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&amp;P etc. required for the complete in all respect. and as per direction of Engineer in Charge</p>	-	6.34	Rmt
i	Semi-Skilled	0.27300613496933	1.7308588957055	-
ii	Highly-Skilled	0.27300613496933	1.7308588957055	-
20	<p><b>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position -</b> Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	9	Qntl

i	Un-Skilled	0.8	7.2	-
ii	Highly-Skilled	0.3	2.7	-
iii	Semi-Skilled	0.044	0.396	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	118.71519155345	462	54846.418497692
2	Skilled	54.32276432973	562	30529.393553308
3	Highly-Skilled	28.798500559684	612	17624.682342527
4	Semi-Skilled	45.213600440158	512	23149.363425361
<b>Total:</b>				<b>126149.85781889</b>

## MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</b>	-	<b>15.721376</b>	Cum

2	<b>Earth Work (AR0115)</b> :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	<b>14.034896</b>	Cum
i)	<b>BRM029</b> : Sand for filling and road blinding	1	14.034896	1 Cum
3	<b>Concrete (AR0303)</b> :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	<b>3.28112</b>	Cum
i)	<b>BRM340</b> : Cement	2.29	7.5137648	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	1.5749376	1 Cum
iii)	<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	3.1498752	1 Cum.

4	<p><b>Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth</b>  - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance <math>\pm 8</math> percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&amp;P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	6.72635	Cum
i)	<b>BRM340</b> : Cement	0.672	4.5201072	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1.883378	1 Cum
iii)	<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2$ %	350	2354.2225	1000 Nos
5	<p><b>Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure -</b>  Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance <math>\pm 8</math> percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&amp;P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	8.865775	Cum

i)	<b>BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK</b>	1	8.865775	1 Cum
ii)	<b>BRM340 : Cement</b>	0.672	5.9578008	1 Qntl.
iii)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.28	2.482417	1 Cum
iv)	<b>BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance <math>\pm</math> 2 %</b>	350	3103.02125	1000 Nos
6	<b>R.C.C. Work (AR0404Aa) :.Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&amp;P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)</b>	-	<b>0.0397709456</b>	Cum
i)	<b>BRM340 : Cement</b>	3.4733	0.13813642535248	1 Qntl.
ii)	<b>BRM028 : Screened and washed sharp sand for mortar</b>	0.45	0.01789692552	1 Cum

iii)	<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.014317540416	1 Cum.
iv)	<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.021476310624	1 Cum.
v)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.000159282637128	1Cum.
vi)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.189	0.0075167087184	1Mtr.
7	<b>R.C.C. Work (AR0404Ab)</b> :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	<b>1.14125</b>	Cum
i)	<b>BRM340</b> : Cement	3.4733	3.963903625	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	0.5135625	1 Cum

iii)	<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.41085	1 Cum.
iv)	<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.616275	1 Cum.
v)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	0.0152356875	1Cum.
vi)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.63	0.7189875	1Mtr.
8	<b>R.C.C. Work (AR0404Ac)</b> :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	<b>2.712875</b>	Cum
i)	<b>BRM340</b> : Cement	3.4733	9.4226287375	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1.22079375	1 Cum

iii)	<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.976635	1 Cum.
iv)	<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1.4649525	1 Cum.
v)	<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	11.98982235	1Mtr
vi)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	0.112662985875	1Cum.
9	<b>R.C.C. Work (AR0404Ag)</b> :Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	<b>3.479592</b>	Cum
i)	<b>BRM340</b> : Cement	3.4733	12.0856668936	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1.5658164	1 Cum

iii)	<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.25265312	1 Cum.
iv)	<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1.87897968	1 Cum.
v)	<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	21.6486295872	1Mtr
vi)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	0.1747353673824	1Cum.
10	<b>Plastering (AR1027) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T &amp; P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</b>	-	<b>17.3455</b>	Sqm
i)	<b>BRM340</b> : Cement	0.0372	0.6452526	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.0075	0.13009125	1 Cum

11	<b>Plastering (AR1004)</b> <b>::12mm thick cement plaster (1:6) over Brick work in inside</b> - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	<b>36.7956</b>	Sqm
i)	<b>BRM340</b> : Cement	0.0358	1.31728248	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.015	0.551934	1 Cum
12	<b>Plastering (AR1014)</b> <b>::16mm thick cement Plaster in CM (1:6) over brick work in inside.</b> - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	<b>24.4496</b>	Sqm
i)	<b>BRM340</b> : Cement	0.043	1.0513328	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.018	0.4400928	1 Cum

13	<p><b>Other Building Items. (AR1901B) :.Vitrified Tile 600mmx600mm Plain Ivory -</b>  Supplying, fitting &amp; fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&amp;P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	-	16.2936	Sqm
i)	<b>BRM174</b> : White Cement.	0.0076	0.12383136	1Qntl
ii)	<b>BRM340</b> : Cement	0.1074	1.74993264	1 Qntl.
iii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.021	0.3421656	1 Cum
iv)	<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	16.2936	1 Sqm.

14	<p><b>Flooring (AR0817aa)</b>  <b>:.Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) -</b>  Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	17.7328	Sqm
i)	<p><b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)</p>	1	17.7328	1 Sqm.
ii)	<p><b>BRMMR0027</b> : Wax Polish</p>	1	17.7328	1 Sqm
iii)	<p><b>BRM340</b> : Cement</p>	0.1375	2.43826	1 Qntl.
iv)	<p><b>BRM028</b> : Screened and washed sharp sand for mortar</p>	0.015	0.265992	1 Cum

15	<b>Flooring (AR0816j)</b> :.Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 - Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the Chequered tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.	-	7.3744	Sqm
i)	<b>BRM134</b> : Chequered Tiles.	1	7.3744	1 Sqm.
ii)	<b>BRMMR0027</b> : Wax Polish	1	7.3744	1 Sqm
iii)	<b>BRM340</b> : Cement	0.2737	2.01837328	1 Qntl.
iv)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.013	0.0958672	1 Cum
16	<b>Painting(AR0901d)</b> :.Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	31.8364	Sqm
i)	<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.084	2.6742576	1 Ltr

17	<b>Painting(AR0920)</b> :.Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	<b>31.8364</b>	Sqm
i)	<b>BRM140</b> : Plastic Emulsion paint	0.125	3.97955	1 Litre
18	<b>Painting(AR0918cb)</b> :.Finishing wall two coats with weather coat with one coat waterbound Primer - Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	<b>42.7246</b>	Sqm
i)	<b>BRM255</b> : Weather Coat (I.S.I.)	0.125	5.340575	1 Ltr
ii)	<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.090322580645161	3.8589961290323	1 Ltr

19	<p><b>Other Building Items. (AR1911) :Stainless steel of 304 grade in hand railing using 50mm dia of 2mm -</b>  Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&amp;P etc. required for the complete in all respect. and as per direction of Engineer in Charge</p>	-	6.34	Rmt
i)	<b>BRMMR0024</b> : Buffing, Polishing etc.	0.30674846625767	1.9447852760736	L.S.
ii)	<b>BRMMR0023</b> : Fabrication	10.478527607362	66.433865030675	kg
iii)	<b>BRMMR0022</b> : Stainless steel square pipe bracing of size 32mmx32mmx2mm in 3 rows	5.101226993865	32.341779141104	kg
iv)	<b>BRMMR0021</b> : Balustrade of size 30mmx32mmx2mm	1.8773006134969	11.902085889571	kg
v)	<b>BRMMR0020</b> : Railing 50mm outer dia of 2mm thick	3.5	22.19	kg

20	<b>R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position -</b> Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	9	Qntl
i)	<b>BRM162</b> : Binding Wire.	0.8	7.2	1 Kg.
ii)	<b>BRM341</b> : Steel	1.05	9.45	1 Qntl.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM029</b>	14.034896	1 Cum	829.69	11644.61286224
2	<b>BRM340</b>	52.822442281452	1 Qntl.	582.935	30792.050391338
3	<b>BRM028</b>	11.08494502552	1 Cum	834.63	9251.8276666498
4	<b>BRM044</b>	3.1498752	1 Cum.	1763.45	5554.64742144
5	<b>BRM005</b>	5457.24375	1000 Nos	6.04185	32971.848150937
6	<b>BRMMR0025</b>	8.865775	1 Cum	33	292.570575
7	<b>BRM060</b>	2.654455660416	1 Cum.	2237.95	5940.539045228
8	<b>BRM052</b>	3.981683490624	1 Cum.	2205.14	8780.1695325146
9	<b>BRM104</b>	0.30279332339453	1Cum.	58620.646	17749.940221874
10	<b>BRM092</b>	0.7265042087184	1Mtr.	276.666	200.99901340928
11	<b>BRM084</b>	33.6384519372	1Mtr	297.726	10015.041741455
12	<b>BRM174</b>	0.12383136	1Qntl	2045.055	253.2419419248
13	<b>BRM131</b>	34.0264	1 Sqm.	664.6084447	22614.23278274
14	<b>BRMMR0027</b>	25.1072	1 Sqm	8.5	213.4112
15	<b>BRM134</b>	7.3744	1 Sqm.	225.5	1662.9272
16	<b>BRM253</b>	6.5332537290323	1 Ltr	155.99055	1019.1258424813
17	<b>BRM140</b>	3.97955	1 Litre	249.73055	993.8152102525
18	<b>BRM255</b>	5.340575	1 Ltr	193.39055	1032.8167365663
19	<b>BRMMR0024</b>	1.9447852760736	L.S.	178.42	346.98858895706

20	<b>BRMMR0023</b>	66.433865030675	kg	10	664.33865030675
21	<b>BRMMR0022</b>	32.341779141104	kg	256.62	8299.5473631902
22	<b>BRMMR0021</b>	11.902085889571	kg	256.62	3054.3132809816
23	<b>BRMMR0020</b>	22.19	kg	240.24	5330.9256
24	<b>BRM162</b>	7.2	1 Kg.	90.1	648.72
25	<b>BRM341</b>	9.45	1 Qntl.	6231.605	58888.66725
					<b>Total: 238217.31826949</b>

#### ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM029</b>	14.034896	1 Cum	274.25	3849.070228
2	<b>BRM028</b>	11.08494502552	1 Cum	274.25	3040.0461732489
3	<b>BRM044</b>	3.1498752	1 Cum.	444.5	1400.1195264
4	<b>BRM060</b>	2.654455660416	1 Cum.	444.5	1179.9055410549
5	<b>BRM052</b>	3.981683490624	1 Cum.	444.5	1769.8583115824
					<b>Total: 11238.999780286</b>

#### ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ 1%	Rs. 3895.5741027336
2	Display Citizen Board @ Rs. 5000	Rs. 5000
3	Any Other Lumpsum @ Rs. 1547	Rs. 1547
		<b>Total Addition Component Amount (in Rs.): 10442.574102734</b>

**Total Net Amount (in Rs.): 399999.98437609**