

ESTIMATION DPR

State	Odisha	District	Mayurbhanj	Block	Betnoti	Gram Panchayat	Betnoti
--------------	--------	-----------------	------------	--------------	---------	-----------------------	---------

Work Code	OD/365/3491/120112/390498/00074169 (Construction of cc road from betnoti millsahi Damdar das house to Dinesh Mishra house at Betnoti)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Betnoti	Proposal Date	-
Date of Commencement	-	Date of Completion	
Scheme Name	Bikashita Gaon Bikashita Odisha	Scheme Component Name	Viksit Gaon Vikshit Odisha (VGVO)
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	278
Fund Sanction Amount (in Rs.)	500000

ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;">Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	8.12025	240.77592	1955.16066438
2	<p style="text-align: center;">Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	20.5365	1428.234132	29330.930251818

3	<p style="text-align: center;">Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	32.76025	6571.9833723	215299.81827239
4	<p style="text-align: center;">R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	Sqm	72.38	216.39264180804	15662.499414066

5	<p align="center">Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	Cum	28.105	8068.6119571	226768.3390543
Total Amount (in Rs.): 489016.74765695					

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Meaurement Qty)	Unit
1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	8.12025	Cum

	i	Un-Skilled	0.516	4.190049	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	20.5365	Cum
	i	Un-Skilled	0.1236	2.5383114	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	32.76025	Cum
	i	Skilled	0.18	5.896845	-
	ii	Un-Skilled	3.9	127.764975	-

4	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	72.38	Sqm
i	Semi-Skilled	0.05	3.619	-
ii	Skilled	0.05	3.619	-
5	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	28.105	Cum
i	Un-Skilled	4.6	129.283	-
ii	Skilled	0.68	19.1114	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	263.7763354	462	121864.6669548
2	Skilled	28.627245	562	16088.51169
3	Semi-Skilled	3.619	512	1852.928
Total:				139806.1066448

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	8.12025	Cum
2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	20.5365	Cum
i)	BRM029 : Sand for filling and road blinding	1	20.5365	1 Cum

3	<p>Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	32.76025	Cum
i)	BRM340 : Cement	2.29	75.0209725	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	15.72492	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	31.44984	1 Cum.
4	<p>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	72.38	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.1932546	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	9.11988	1Mtr.

5	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.	-	28.105	Cum
i)	BRM340 : Cement	3.23	90.77915	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	12.64725	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	25.2945	1 Cum.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	20.5365	1 Cum	531.74	10920.07851
2	BRM340	165.8001225	1 Qntl.	632.787	104916.16211641
3	BRM028	28.37217	1 Cum	538.16	15268.7670072
4	BRM044	31.44984	1 Cum.	1792.06	56360.0002704
5	BRM104	0.1932546	1Cum.	58620.646	11328.709494472
6	BRM092	9.11988	1Mtr.	276.666	2523.16072008
7	BRM056	25.2945	1 Cum.	2193.43	55481.715135
Total: 256798.59325356					

ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM029	20.5365	1 Cum	825.25	16947.746625
2	BRM028	28.37217	1 Cum	825.25	23414.1332925
3	BRM044	31.44984	1 Cum.	551.5	17344.58676

4	BRM056	25.2945	1 Cum.	551.5	13949.91675
					Total: 71656.3834275

ADDITION COMPONENT

Sl.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ 1%	Rs. 4890.1674765695
2	Display Citizen Board @ Rs. 5000	Rs. 5000
3	Any Other Lumpsum @ Rs. 1093	Rs. 1093
		Total Addition Component Amount (in Rs.): 10983.16747657

Total Net Amount (in Rs.): 499999.91513352