

## ESTIMATION DPR

<b>State</b>	Odisha	<b>District</b>	Mayurbhanj	<b>Block</b>	Bangriposi	<b>Gram Panchayat</b>	Bangriposi
--------------	--------	-----------------	------------	--------------	------------	-----------------------	------------

<b>Work Code</b>	OD/365/3489/120081/389463/00078979 (Creation of Facility Center at Bangriposi Block Campus)
<b>Project Category</b>	Building

<b>Financial Year</b>	2025-26	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Bangriposi	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	-	<b>Date of Completion</b>	
<b>Scheme Name</b>	Bikashita Gaon Bikashita Odisha	<b>Scheme Component Name</b>	Viksit Gaon Vikshit Odisha (VGVO)
<b>Project Sub-Category</b>	Office Building	<b>Project Type</b>	New Work
<b>Name of Executant</b>			

**Administrative Approval Details**

<b>Approval No.</b>	
---------------------	--

**Technical Sanction Details**

<b>Technical Sanction No.</b>	
<b>Fund Sanction No.</b>	278
<b>Fund Sanction Amount (in Rs.)</b>	1000000

**ACTIVITY STATEMENT**

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;"><b>Earth Work (AR0102aa)</b>  <b>: Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b>  Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	46.8926208	240.77592	11290.613914331
2	<p style="text-align: center;"><b>Earth Work (AR0115) :</b>  <b>Filling foundation and plinth with sand well watered and rammed -</b>  Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	58.47285261536	1025.042132	59937.13750897

3	<p style="text-align: center;"><b>Concrete (AR0303a) :</b>  <b>Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	14.670008460442	5685.4877883	83406.153956101
---	--	-----	-----------------	--------------	-----------------

4	<p style="text-align: center;"><b>R.C.C. Work (AR0404A) : Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b></p> <p>Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)</p>	Cum	32.753754096758	6170.337792491	202101.72674918
---	---	-----	-----------------	----------------	-----------------

5	<p style="text-align: center;"><b>R.C.C. Work (AR0409) :</b>  <b>Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position -</b>  Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in- charge.</p>	Qntl	31.084	8409.9650204	261415.35269411
6	<p style="text-align: center;"><b>R.C.C. Work (AR0410c) :</b>  <b>R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	Sqm	57.53668596	216.23489289764	12441.439126246

7	<p style="text-align: center;"><b>R.C.C. Work (AR0410d) :</b>  <b>Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting -</b>  Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, girder and bressmer, etc. Data for 4.2sqm</p>	Sqm	53.3875264964	1047.3822930467	55917.149921891
8	<p style="text-align: center;"><b>R.C.C. Work (AR0410e) :</b>  <b>Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting -</b>  Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm</p>	Sqm	20.24449273	499.15267251462	10105.092649882

9	<p><b>R.C.C. Work (AR0410a) : Centring &amp; Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height</b></p>	Sqm	79.6457419	662.689943368	52780.432189213
10	<p><b>Masonry Brick Work (AR0603b) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance <math>\pm 8</math> percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&amp;P required for the work, etc. complete and as per direction of Engineer-in-charge.</b></p>	Cum	9.57768470944	5094.99332244	48798.239639032

11	<p style="text-align: center;"><b>Masonry</b></p> <p><b>Brick Work (AR0603bi) :</b>  <b>Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure -</b>  Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&amp;P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	Cum	36.71488894016	5128.32332244	188285.82123262
<b>Total Amount (in Rs.): 986479.15958158</b>					

## LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<p><b>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b>  Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	46.8926208	Cum

	i	Un-Skilled	0.516	24.1965923328	-
2		<b>Earth Work (AR0115)</b> <b>: Filling foundation and plinth with sand well watered and rammed</b> - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	58.47285261536	Cum
	i	Un-Skilled	0.1236	7.2272445832585	-
3		<b>Concrete (AR0303a)</b> <b>: Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal</b> - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	14.670008460442	Cum
	i	Un-Skilled	3.9	57.213032995724	-
	ii	Skilled	0.18	2.6406015228796	-

4	<b>R.C.C. Work (AR0404A) :</b> <b>Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	32.753754096758	Cum
i	Un-Skilled	1.3333	43.670580337207	-
ii	Skilled	0.1	3.2753754096758	-
iii	Semi-Skilled	0.0573	1.8767901097442	-

5	<p><b>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position -</b>  Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	31.084	Qntl
i	Un-Skilled	0.8	24.8672	-
ii	Highly-Skilled	0.3	9.3252	-
iii	Semi-Skilled	0.044	1.367696	-
6	<p><b>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b>  Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	57.53668596	Sqm
i	Semi-Skilled	0.05	2.876834298	-

	ii	Skilled	0.05	2.876834298	-
7		<b>R.C.C. Work (AR0410d) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm</b>	-	53.3875264964	Sqm
	i	Semi-Skilled	0.6547619047619	34.95611853931	-
	ii	Skilled	0.6547619047619	34.95611853931	-
8		<b>R.C.C. Work (AR0410e) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm</b>	-	20.24449273	Sqm
	i	Semi-Skilled	0.16025641025641	3.2443097323718	-
	ii	Skilled	0.16025641025641	3.2443097323718	-

9	<p><b>R.C.C. Work (AR0410a) : Centring &amp; Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas</b> - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height</p>	-	79.6457419	Sqm	
	i	Semi-Skilled	0.305555555555556	24.336198913889	-
	ii	Skilled	0.305555555555556	24.336198913889	-
10	<p><b>Masonry Brick Work (AR0603b) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth</b> - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance <math>\pm 8</math> percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&amp;P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	9.57768470944	Cum	
	i	Un-Skilled	2.96	28.349946739942	-

	ii	Skilled	1.05	10.056568944912	-
	iii	Highly-Skilled	0.35	3.352189648304	-
11		<b>Masonry Brick Work (AR0603bi) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure -</b> Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm <sup>2</sup> with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	36.71488894016	Cum
	i	Un-Skilled	2.96	108.67607126287	-
	ii	Skilled	1.05	38.550633387168	-
	iii	Highly-Skilled	0.35	12.850211129056	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	294.20066825181	462	135920.70873233
2	Skilled	119.93664074821	562	67404.392100492
3	Semi-Skilled	68.657947593314	512	35152.869167777

4	Highly-Skilled	25.52760077736	612	15622.891675744
				<b>Total: 254100.86167635</b>

## MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	<b>46.8926208</b>	Cum
2	<b>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed -</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	<b>58.47285261536</b>	Cum
i)	<b>BRM029 : Sand for filling and road blinding</b>	1	58.47285261536	1 Cum

3	<p><b>Concrete (AR0303a)</b>  <b>:.Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal -</b>  Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	<b>14.670008460442</b>	Cum
i)	<b>BRM340</b> : Cement	2.29	33.594319374412	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	7.0416040610122	1 Cum
iii)	<b>BRM045</b> : Granite Stone broken metal 40mm. size (Hand broken)	0.96	14.083208122024	1 Cum.
4	<p><b>R.C.C. Work (AR0404A)</b>  <b>:.Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips -</b>  Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&amp;P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)</p>	-	<b>32.753754096758</b>	Cum
i)	<b>BRM340</b> : Cement	3.4733	113.76361410427	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	14.739189343541	1 Cum

iii)	<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	11.791351474833	1 Cum.
iv)	<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	17.687027212249	1 Cum.
5	<b>R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position -</b> Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	<b>31.084</b>	Qntl
i)	<b>BRM162</b> : Binding Wire.	0.8	24.8672	1 Kg.
ii)	<b>BRM341</b> : Steel	1.05	32.6382	1 Qntl.

6	<p><b>R.C.C. Work (AR0410c) :R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	<b>57.53668596</b>	Sqm
i)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.1536229515132	1Cum.
ii)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.126	7.24962243096	1Mtr.
7	<p><b>R.C.C. Work (AR0410d) :Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm</p>	-	<b>53.3875264964</b>	Sqm
i)	<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.55238095238095	29.490252731345	1Mtr
ii)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0051904761904762	0.27710668514798	1Cum.

8	<b>R.C.C. Work (AR0410e) :.Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm</b>	-	<b>20.24449273</b>	Sqm
i)	<b>BRM094</b> : Non-sal bullahs 125mm. mean dia of any length.	0.26923076923077	5.4504403503846	1Mtr.
ii)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0052948717948718	0.10719199355756	1Cum.
9	<b>R.C.C. Work (AR0410a) :.Centring &amp; Shuttering for R.C.C. floor and roof slabs, landings,balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height</b>	-	<b>79.6457419</b>	Sqm
i)	<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.622222222222222	49.557350515556	1Mtr
ii)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0050222222222222	0.39999861487556	1Cum.

10	<p><b>Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth</b>  - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance <math>\pm 8</math> percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&amp;P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	<b>9.57768470944</b>	Cum
i)	<b>BRM340</b> : Cement	0.672	6.4362041247437	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	2.6817517186432	1 Cum
iii)	<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm <sup>2</sup> with dimensional tolerance $\pm 2$ %	350	3352.189648304	1000 Nos
11	<p><b>Masonry Brick Work (AR0603bi) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure -</b>  Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance <math>\pm 8</math> percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&amp;P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	<b>36.71488894016</b>	Cum

i)	<b>BRMMR0025</b> : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	36.71488894016	1 Cum
ii)	<b>BRM340</b> : Cement	0.672	24.672405367788	1 Qntl.
iii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	10.280168903245	1 Cum
iv)	<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm$ 2 %	350	12850.211129056	1000 Nos

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM029</b>	58.47285261536	1 Cum	401.54	23479.189239172
2	<b>BRM340</b>	178.46654297121	1 Qntl.	632.787	112931.30832712
3	<b>BRM028</b>	34.742714026441	1 Cum	407.96	14173.637614227
4	<b>BRM045</b>	14.083208122024	1 Cum.	1063.37	14975.661020717
5	<b>BRM060</b>	11.791351474833	1 Cum.	1682.05	19833.642748243
6	<b>BRM052</b>	17.687027212249	1 Cum.	1684.34	29790.96741468
7	<b>BRM162</b>	24.8672	1 Kg.	90	2238.048
8	<b>BRM341</b>	32.6382	1 Qntl.	6201.497	202405.6993854
9	<b>BRM104</b>	0.9379202450943	1Cum.	58573.086	54936.88317705
10	<b>BRM092</b>	7.24962243096	1Mtr.	229.106	1660.9319966675
11	<b>BRM084</b>	79.0476032469	1Mtr	250.166	19775.022713864
12	<b>BRM094</b>	5.4504403503846	1Mtr.	240.106	1308.6834307694
13	<b>BRM005</b>	16202.40077736	1000 Nos	6.01135	97398.301912983
14	<b>BRMMR0025</b>	36.71488894016	1 Cum	33	1211.5913350253
<b>Total: 596119.56831592</b>					

## ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM029</b>	58.47285261536	1 Cum	556.25	32525.524267294
2	<b>BRM028</b>	34.742714026441	1 Cum	556.25	19325.634677208
3	<b>BRM045</b>	14.083208122024	1 Cum.	565.5	7964.0541930048
4	<b>BRM060</b>	11.791351474833	1 Cum.	565.5	6668.009259018
5	<b>BRM052</b>	17.687027212249	1 Cum.	565.5	10002.013888527
<b>Total: 76485.236285052</b>					

**ADDITION COMPONENT**

<b>Sl.No.</b>	<b>Item Name</b>	<b>Amount (in Rs.)</b>
1	Provision for Contingency @ Rs. 10000	Rs. 10000
2	Display Citizen Board @ Rs. 3520.84	Rs. 3520.84
<b>Total Addition Component Amount (in Rs.): 13520.84</b>		

**Total Net Amount (in Rs.): 999999.99958158**