

ESTIMATION DPR							
State	Odisha	District	Jagatsinghpur	Block	Tirtol	Gram Panchayat	Bodhei

Work Code	OD/355/3393/118208/397565/00104090 (Installation of Solar LED Mini Mast Light near Jagannath Mahapurusha Pitha Radhugada of Bindhapada, GP- Bodhei)						
Project Category	Rural Electrification						

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Tirtol	Proposal Date	-
Date of Commencement	-	Date of Completion	
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	LED Street Lighting	Project Type	New Work
Name of Executant			

Administrative Approval Details

Approval No.	
--------------	--

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	100000

ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;">R.C.C. Work (AR0404Aa) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concreate, pre-cast slabs etc.)</p>	Cum	0.469625	7678.4658097439	3605.999505901
Total Amount (in Rs.): 3605.999505901					

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Meaurement Qty)	Unit
--------	---------------	--	-----------------------------	------

1	R.C.C. Work (AR0404Aa) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)	-	0.469625	Cum
i	Un-Skilled	1.3333	0.6261510125	-
ii	Skilled	0.175	0.082184375	-
iii	Semi-Skilled	0.1323	0.0621313875	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	0.6261510125	462	289.281767775
2	Skilled	0.082184375	562	46.18761875
3	Semi-Skilled	0.0621313875	512	31.8112704
Total: 367.280656925				

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<p>R.C.C. Work (AR0404Aa) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)</p>	-	0.469625	Cum
i)	BRM340 : Cement	3.4733	1.6311485125	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	0.21133125	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	0.169065	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	0.2535975	1 Cum.

v)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	0.001880848125	1Cum.
vi)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	0.088759125	1Mtr.

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM340	1.6311485125	1 Qntl.	588.347	959.68133388384
2	BRM028	0.21133125	1 Cum	1577.62	333.400406625
3	BRM060	0.169065	1 Cum.	2924.58	494.4441177
4	BRM052	0.2535975	1 Cum.	2888.2	732.4402995
5	BRM104	0.001880848125	1Cum.	58573.086	110.16707897856
6	BRM092	0.088759125	1Mtr.	229.106	20.33524809225
Total: 2650.4684847797					

ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM028	0.21133125	1 Cum	199.25	42.1077515625
2	BRM060	0.169065	1 Cum.	444.5	75.1493925
3	BRM052	0.2535975	1 Cum.	444.5	112.72408875
Total: 229.9812328125					

ADDITION COMPONENT

SI.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ Rs. 1000	Rs. 1000
2	Display Citizen Board @ Rs. 380	Rs. 380
3	Any Other Lumpsum @ Rs. 95000	Rs. 95000
Total Addition Component Amount (in Rs.): 96380		

Total Net Amount (in Rs.): 99985.999505901