

Detailed Estimate

OD/373/3575/121561/384543/00063163 : Const.of CC Road from Thayar House to Abit House at Gudgudjore,Santoshpur GP

Block : Bisra, Gram Panchayat : Santoshpur

Created By:Punam Rashid Khan

1. Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift								
Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Cut Off	2.000	27.500	0.250	0.250	1.000	3.438	-
Total Quantity					3.4375 cum (cum)		3.4375 Cum (Cubic Meter)	
Amount					3.4375 X 240.77592		827.67	
2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed								
Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Road	1.000	27.500	5.300	0.100	1.000	14.575	-
Total Quantity					14.575 cum (cum)		14.575 Cum (Cubic Meter)	
Amount					14.575 X 647.009232		9430.16	
3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal								
Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Cut Off	2.000	27.500	0.250	0.100	1.000	1.375	-
ii	Road	1.000	27.500	5.300	0.100	1.000	14.575	-

Total Quantity		15.95 cum (cum)		15.95 Cum (Cubic Meter)				
Amount		15.95 X 5350.60681712		85342.18				
4. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum								
Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Road	1.000	27.500	5.300	0.100	1.000	14.575	-
Total Quantity		14.575 cum (cum)		14.575 Cum (Cubic Meter)				
Amount		14.575 X 6857.21839544		99943.96				
5. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc								
Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Foundation	2.000	27.500	1.000	0.100	1.000	5.500	-
Total Quantity		5.5 Sqm (Sqm)		5.5 Sqm (Square Meter)				
Amount		5.5 X 216.70813962884		1191.89				
Total Amount		196735.86						
Addition								
Provision for Contingency (+) @		1000.00						
Display Citizen Board (+) @		1000.00						
Any Other Lumpsum (+) @		1264.00						
Provision for survey investigation and quality control (+) @								
Total Addition		3264.00						

Grand Net Total Amount	199999.86
-------------------------------	------------------

**Punam Rashid Khan
JE
Bisra Block**

**Sri Rajat Chandra Singh
AEE
Bisra Block**

**BDO Bisra
BDO
Bisra Block**