

Detailed Estimate

OD/346/3305/116247/393087/00063877 : repair and restoration of road from madhab mandir to sania house ,
naimchanaranpur

Block : Nilgiri, Gram Panchayat : Narasinghpur

Created By: Bharat Singh

1. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum								
Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i		1.000	615.000	0.290	0.000	0.000	178.350	-
Total Quantity					178.35 Cft (Cubic Foot)		5.05030128 Cum (Cubic Meter)	
Amount					5.05030128 X 7610.23929188		38434.00	
Total Amount							38434.00	
Addition								
Provision for Contingency (+) @							390.00	
Display Citizen Board (+) @							175.00	
Any Other Lumpsum (+) @								
Provision for survey investigation and quality control (+) @								
Total Addition							565.00	
Grand Net Total Amount							38999.00	

Bharat Singh
JE
Nilgiri Block

SARAT KUMAR UPADHYAYA
AEE
Nilgiri Block

Bikram Kishore Parida
BDO
Nilgiri Block