

Detailed Estimate

OD/361/3449/119387/387057/00063751 : Improvement of Road at SINGdov Village of Bancho GP

Block : Hatadihi, Gram Panchayat : Bancho

Created By:PRAFULLA CHANDRA BEHERA

1. Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift								
Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Earth work in excavation of foundation etc complete	1.000	61.000	3.600	0.150	0.000	32.940	-
Total Quantity					32.94 cum (cum)		32.94 Cum (Cubic Meter)	
Amount					32.94 X 240.77592		7931.16	
2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed								
Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Filling (F&P) with sand well watered rammed etc complete	1.000	61.000	3.600	0.150	0.000	32.940	-
Total Quantity					32.94 cum (cum)		32.94 Cum (Cubic Meter)	
Amount					32.94 X 978.652832		32236.82	
3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal								
Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction

i	C.C. (1:3:6) using 40 mm size h.g. metal	1.000	61.000	3.600	0.100	0.000	21.960	-
Total Quantity					21.96 cum (cum)		21.96 Cum (Cubic Meter)	
Amount					21.96 X 5886.65286574		129270.90	
4. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc								
Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Rigid & smooth centering for casting of mass concrete	2.000	61.000	0.000	0.175	0.000	21.350	-
Total Quantity					21.35 Sqm (Sqm)		21.35 Sqm (Square Meter)	
Amount					21.35 X 216.23489289764		4616.61	
5. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum								
Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	C.C (1:2:4) using 12 mm size h.g. c.b. chips	1.000	61.000	3.600	0.075	0.000	16.470	-
Total Quantity					16.47 cum (cum)		16.47 Cum (Cubic Meter)	
Amount					16.47 X 7349.66267538		121048.94	
Total Amount							295104.44	
Addition								
Provision for Contingency (+) @							2951.04	

Display Citizen Board (+) @	1944.51
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	
Total Addition	4895.55
Grand Net Total Amount	299999.99

PRAFULLA CHANDRA BEHERA
JE
Hatadihi Block

MADAN MOHAN BEHERA
AEE
Hatadihi Block

RANJAN KUMAR PARIDA
BDO
Hatadihi Block