

Detailed Estimate

OD/365/3491/120123/390560/00064906 : CONSTRUCTION OF CC ROAD FROM FUTI MAHANTA HOUSE TO CHHATIS

MOHANTA HOUSE AT PURINDA

Block : Betnoti, Gram Panchayat : Purinda

Created By: SNEHALATA PATI

1. Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift								
Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	cutoff	2.000	38.000	0.250	0.150	0.000	2.850	-
ii	End cutoff	2.000	2.500	0.250	0.150	0.000	0.188	-
Total Quantity					3.0375 cum (cum)		3.0375 Cum (Cubic Meter)	
Amount					3.0375 X 240.77592		731.36	
2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed								
Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	cutoff wall	2.000	38.000	0.250	0.100	0.000	1.900	-
ii	End cutoff	2.000	2.500	0.250	0.100	0.000	0.125	-
iii	inside ropad	1.000	37.500	2.500	0.100	0.000	9.375	-
Total Quantity					11.4 cum (cum)		11.4 Cum (Cubic Meter)	
Amount					11.4 X 1428.234132		16281.87	
3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal								
Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.								

SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	cutoff wall	2.000	38.000	0.250	0.200	0.000	3.800	-
ii	End cutoff	2.000	2.500	0.250	0.200	0.000	0.250	-
iii	inside road	1.000	37.500	2.500	0.100	0.000	9.375	-
Total Quantity					13.425 cum (cum)		13.425 Cum (Cubic Meter)	
Amount					13.425 X 6604.7340363		88668.55	
4. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum								
Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	road	1.000	38.000	3.000	0.075	0.000	8.550	-
Total Quantity					8.55 cum (cum)		8.55 Cum (Cubic Meter)	
Amount					8.55 X 8114.8061251		69381.59	
5. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc								
Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	cutoff outer side	2.000	38.000	0.000	0.300	0.000	22.800	-
ii	inside	2.000	37.500	0.000	0.200	0.000	15.000	-
iii	end	2.000	2.500	0.000	0.200	0.000	1.000	-
iv	outer	2.000	3.000	0.000	0.300	0.000	1.800	-
Total Quantity					40.6 Sqm (Sqm)		40.6 Sqm (Square Meter)	

Amount	40.6 X 216.23489289764	8779.14
Total Amount		183842.51
Addition		
Provision for Contingency (+) @		1838.43
Display Citizen Board (+) @		2500.00
Any Other Lumpsum (+) @		1819.06
Provision for survey investigation and quality control (+) @		
Total Addition		6157.49
Grand Net Total Amount		189999.99

SNEHALATA PATI
JE
Betnoti Block

SOUMYASHREE BHOI
AEE
Betnoti Block

SUSANTA KUMAR SUTAR
BDO
Betnoti Block