

## Detailed Estimate

OD/346/3305/116250/393099/00064596 : Repair and restoration of road from Mahadfev temple to Rabi singh house  
Block : Nilgiri, Gram Panchayat : Radhakishorepur  
Created By: Bharat Singh

<b>1. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum</b>								
Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i		1.000	805.880	0.330	0.000	0.000	265.940	-
Total Quantity					265.9404 Cft (Cubic Foot)		7.53058111872 Cum (Cubic Meter)	
Amount					7.53058111872 X 7771.9804414		58527.53	
Total Amount							58527.53	
<b>Addition</b>								
Provision for Contingency (+) @							372.00	
Display Citizen Board (+) @							500.00	
Any Other Lumpsum (+) @							600.00	
Provision for survey investigation and quality control (+) @								
Total Addition							1472.00	
Grand Net Total Amount							59999.53	

Bharat Singh  
JE  
Nilgiri Block

M Mohanty  
AEE  
Nilgiri Block

Bikram Kishore Parida  
BDO  
Nilgiri Block