

## Detailed Estimate

**OD/358/3410/275645/423969/00065255 : CONSTRUCTION OF CC ROAD FROM MAJHIPADA TO THAKURANI  
MANDIR,GP-BAGAD**

**Block : Dharamagarh, Gram Panchayat : Bagad**

**Created By:Romanchal Bhoi**

<b>1. Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b>								
Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	CUTOFF WALL	2.000	46.500	0.200	0.200	0.000	3.720	-
Total Quantity					3.72 cum (cum)		3.72 Cum (Cubic Meter)	
Amount					3.72 X 240.77592		895.69	
<b>2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed</b>								
Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	CUT OFF WALL	2.000	46.500	0.200	0.100	0.000	1.860	-
ii	ROAD	1.000	46.500	3.250	0.100	0.000	15.113	-
Total Quantity					16.9725 cum (cum)		16.9725 Cum (Cubic Meter)	
Amount					16.9725 X 571.057232		9692.27	
<b>3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b>								
Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction

i	CUTOFF WALL	2.000	46.500	0.200	0.150	0.000	2.790	-
ii	ROAD	1.000	46.500	3.250	0.100	0.000	15.113	-
Total Quantity					17.9025 cum (cum)		17.9025 Cum (Cubic Meter)	
Amount					17.9025 X 5315.8315253		95166.67	
<b>4. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum</b>								
Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	ROAD	1.000	46.500	3.650	0.075	0.000	12.729	-
Total Quantity					12.729375 cum (cum)		12.729375 Cum (Cubic Meter)	
Amount					12.729375 X 6851.5981151		87216.56	
<b>5. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc</b>								
Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	CUT OFF WALL	2.000	46.500	0.000	0.150	0.000	13.950	-
Total Quantity					13.95 Sqm (Sqm)		13.95 Sqm (Square Meter)	
Amount					13.95 X 216.39264180804		3018.68	
<b>Total Amount</b>							<b>195989.87</b>	
<b>Addition</b>								
Provision for Contingency (+) @							2000.00	

Display Citizen Board (+) @	2000.00
Any Other Lumpsum (+) @	10.00
Provision for survey investigation and quality control (+) @	
<b>Total Addition</b>	<b>4010.00</b>
<b>Grand Net Total Amount</b>	<b>199999.87</b>

**Romanchal Bhoi**  
**JE**  
**Dharamagarh Block**

**sarbeswar padhan**  
**AEE**  
**Dharamagarh Block**

**SADASIV NAYAK**  
**BDO**  
**Dharamagarh Block**