

Detailed Estimate

**OD/353/3360/117489/413571/00071642 : Construction of CC road with drain at Christian Sahi Adava Convergence
with MGNREGS**

Block : Mohona, Gram Panchayat : Adava

Created By:Pradeepta Kumar Sethi

1. Earth Work (AR0103a) : Earth work in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume within 50m. Initial lead and 1.5m initial lift									
Earth work in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layer not exceeding 0.3m in depth and as per specification approved by the department									
Sl No	Description	No	L	B	D	CF	Quantity	Deduction	
i	Cut Off	2.000	50.000	0.230	0.230	0.000	5.290	-	
ii	Lavelling	1.000	50.000	3.050	0.150	0.000	22.875	-	
iii	Drain	1.000	50.000	1.200	0.600	0.000	36.000	-	
Total Quantity					64.165 cum (cum)		64.165 Cum (Cubic Meter)		
Amount					64.165 X 312.915372		20078.21		
2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed									
Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.									
Sl No	Description	No	L	B	D	CF	Quantity	Deduction	
i	Cut off	2.000	50.000	0.230	0.100	0.000	2.300	-	
ii		1.000	50.000	3.050	0.100	0.000	15.250	-	
iii		1.000	50.000	1.200	0.100	0.000	6.000	-	
Total Quantity					23.55 cum (cum)		23.55 Cum (Cubic Meter)		
Amount					23.55 X 888.399232		20921.80		
3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal									

Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

SI No	Description	No	L	B	D	CF	Quantity	Deduction
i		2.000	50.000	0.230	0.100	0.000	2.300	-
ii		1.000	50.000	3.050	0.100	0.000	15.250	-
iii		1.000	50.000	1.200	0.100	0.000	6.000	-
iv		2.000	50.000	0.300	0.600	0.000	18.000	-
Total Quantity					41.55 cum (cum)		41.55 Cum (Cubic Meter)	
Amount					41.55 X 5744.54782312		238685.96	

4. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.

SI No	Description	No	L	B	D	CF	Quantity	Deduction
i		1.000	50.000	3.650	0.100	0.000	18.250	-
ii		1.000	50.000	0.600	0.050	0.000	1.500	-
iii		2.000	50.000	0.300	0.050	0.000	1.500	-
Total Quantity					21.25 cum (cum)		21.25 Cum (Cubic Meter)	
Amount					21.25 X 7243.31937744		153920.54	

5. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Drain	2.000	1.000	50.000	0.400	0.000	40.000	-

Total Quantity	40 Sqm (Sqm)	40 Sqm (Square Meter)
Amount	40 X 216.39264180804	8655.71
Total Amount		442262.22
Addition		
Provision for Contingency (+) @		4422.62
Display Citizen Board (+) @		3000.00
Any Other Lumpsum (+) @		
Provision for survey investigation and quality control (+) @		315.00
Total Addition		7737.62
Grand Net Total Amount		449999.84

Pradepta Kumar Sethi
JE
Mohona Block

Asis Kumar Satapathy
AEE
Mohona Block

Rajiv Das
BDO
Mohona Block