

## Detailed Estimate

**OD/357/3408/118563/381073/00070776 : Construction of CC Road from Pravat House to Ganesh House at Shantinagar**

**Block : Lakhanpur, Gram Panchayat : Bandhabahal**

**Created By: Bijaya Laxmi Nayak**

<b>1. Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b>								
Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	Cutt of wall	2.000	46.000	0.250	0.250	0.000	5.750	-
Total Quantity					5.75 cum (cum)		5.75 Cum (Cubic Meter)	
Amount					5.75 X 240.77592		1384.46	
<b>2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed</b>								
Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	cutt of wall	2.000	46.000	0.250	0.100	0.000	2.300	-
ii	subbase	1.000	46.000	2.820	0.100	0.000	12.972	-
Total Quantity					15.272 cum (cum)		15.272 Cum (Cubic Meter)	
Amount					15.272 X 1077.531832		16456.07	
<b>3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b>								
Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.								
Sl No	Description	No	L	B	D	CF	Quantity	Deduction
i	Cutt of wall	2.000	46.000	0.250	0.100	0.000	2.300	-

ii	Sub base	1.000	46.000	2.820	0.100	0.000	12.972	-
Total Quantity					15.272 cum (cum)		15.272 Cum (Cubic Meter)	
Amount					15.272 X 5862.76953714		89536.22	
<b>4. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum</b>								
Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	subbase	1.000	46.000	3.300	0.075	0.000	11.385	-
Total Quantity					11.385 cum (cum)		11.385 Cum (Cubic Meter)	
Amount					11.385 X 7281.74742718		82902.69	
<b>5. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc</b>								
Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Cutt of wall	2.000	46.000	0.000	0.330	0.000	30.360	-
Total Quantity					30.36 Sqm (Sqm)		30.36 Sqm (Square Meter)	
Amount					30.36 X 216.39264180804		6569.68	
<b>Total Amount</b>							<b>196849.12</b>	
<b>Addition</b>								
Provision for Contingency (+) @							2010.00	
Display Citizen Board (+) @							2140.00	
Any Other Lumpsum (+) @								

Provision for survey investigation and quality control (+) @	
<b>Total Addition</b>	<b>4150.00</b>
<b>Grand Net Total Amount</b>	<b>200999.12</b>

**JE**  
**Lakhanpur Block**

**SUSMITA MUNDA**  
**AEE**  
**Lakhanpur Block**

**Binay Patel**  
**BDO**  
**Lakhanpur Block**