

Detailed Estimate

OD/350/3342/117076/399783/00108797 : Improvement of CC road at kulagaonisalo village ward no1 2 3

Block : Nischinta Koili, Gram Panchayat : Asueresswar

Created By:Pradeep Kumar Senapati

1. Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift								
Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	CUTOFFS	2.000	62.000	0.225	0.150	1.000	4.185	-
Total Quantity						4.185 cum (cum)	4.185 Cum (Cubic Meter)	
Amount						4.185 X 240.77592	1007.65	
2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed								
Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	ON ROAD& CUTOOFS	1.000	62.000	3.000	0.070	1.000	13.020	-
Total Quantity						13.02 cum (cum)	13.02 Cum (Cubic Meter)	
Amount						13.02 X 1086.157232	14141.77	
3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal								
Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	ON ROAD	1.000	62.000	3.000	0.100	1.000	18.600	-
ii	CUTOFFS	2.000	62.000	0.225	0.075	1.000	2.093	-
Total Quantity						20.6925 cum (cum)	20.6925 Cum (Cubic Meter)	

Amount	20.6925 X 6090.15944436	126020.62
---------------	----------------------------	-----------

4. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.

SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	WEARING COAT	1.000	62.000	3.000	0.100	1.000	18.600	-
Total Quantity						18.6 cum (cum)	18.6 Cum (Cubic Meter)	
Amount						18.6 X 7559.06192932	140598.55	

5. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	SIDES	2.000	62.000	0.200	1.000	1.000	24.800	-
ii	CUTOOFS	4.000	62.000	0.075	1.000	1.000	18.600	-
Total Quantity						43.4 Sqm (Sqm)	43.4 Sqm (Square Meter)	
Amount						43.4 X 216.39264180804	9391.44	

Total Amount (A) : 291160.03

Additional Components

#	Item Name	Remark	Amount (in Rs.)
1	Provision for Contingency @ Rs.3000	-	3000
2	Display Citizen Board @ Rs.5000	-	5000
3	Any Other Lumpsum @ Rs.839.85	EXPANTION BOARD	839.85

Additional Components Amount (F) : 8839.85

Grand Total Amount (A + F) : 299999.88122808

Pradeep Kumar Senapati
JE
Nischinta Koili Block

Nalinikanta Mohapatra
AEE
Nischinta Koili Block

Dibyendu Kumar Das
BDO
Nischinta Koili Block