

## Detailed Estimate

**OD/350/3339/117006/399474/00112621 : Construction OF CC ROAD FROM RAMESH DAS HOUSE TO ASHOK SETHI  
HOOUSE WARD NO13**

**Block : Mahanga, Gram Panchayat : Madhupur**

**Created By: JAGANNATH PRASADA BARIK**

<b>1. Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b>								
Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	EW	2.000	81.000	0.225	0.150	0.000	5.468	-
<b>Total Quantity</b>						<b>5.4675 cum (cum)</b>	<b>5.4675 Cum (Cubic Meter)</b>	
<b>Amount</b>						<b>5.4675 X 240.77592</b>	<b>1316.44</b>	
<b>2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed</b>								
Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	FS	2.000	81.000	0.225	0.050	0.000	1.823	-
ii	FS	1.000	81.000	2.550	0.075	0.000	15.491	-
<b>Total Quantity</b>						<b>17.31375 cum (cum)</b>	<b>17.31375 Cum (Cubic Meter)</b>	
<b>Amount</b>						<b>17.31375 X 793.620832</b>	<b>13740.55</b>	
<b>3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b>								
Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	CC	2.000	81.000	0.225	0.100	0.000	3.645	-
ii	CC	1.000	81.000	3.000	0.080	0.000	19.440	-

Total Quantity	23.085 cum (cum)	23.085 Cum (Cubic Meter)
Amount	23.085 X 5954.66880286	137463.53

**4. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum**

Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.

SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	CC	1.000	81.000	3.000	0.075	0.000	18.225	-
Total Quantity					18.225 cum (cum)		18.225 Cum (Cubic Meter)	
Amount					18.225 X 7438.54302282		135567.45	

**5. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc**

Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	SHU	2.000	81.000	1.000	0.150	0.000	24.300	-
Total Quantity					24.3 Sqm (Sqm)		24.3 Sqm (Square Meter)	
Amount					24.3 X 216.23489289764		5254.51	

**Total Amount (A) : 293342.48**

**Additional Components**

#	Item Name	Remark	Amount (in Rs.)
1	Provision for Contingency @ 1%	-	2933.4247882497
2	Display Citizen Board @ Rs.3424	-	3424
3	Any Other Lumpsum @ Rs.300	-	300

**Additional Components Amount (F) : 6657.4247882497**

Grand Total Amount (A + F) : 299999.90361322

**JAGANNATH PRASADA BARIK**  
**JE**  
Mahanga Block

**SANDIP KUMAR DAS**  
**AEE**  
Mahanga Block

**SUBHASIS PALATA**  
**BDO**  
Mahanga Block