

Detailed Estimate

OD/352/3350/117269/403319/00100786 : Construction of CC road from Sapanisala to Santoshi Maa Mandira
Block : Dhenkanal Sadar, Gram Panchayat : Kankadahad
Created By: Lambodar Nayak

| 1. Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift | | | | | | | | |
|--|-------------|-------|--------|-------|-------|--------------------------|-------------------------------|-----------|
| Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge | | | | | | | | |
| SI No | Description | No | L | B | D | CF | Quantity | Deduction |
| i | cut off | 2.000 | 70.000 | 0.250 | 0.200 | 1.000 | 7.000 | - |
| Total Quantity | | | | | | 7 cum (cum) | 7 Cum (Cubic Meter) | |
| Amount | | | | | | 7 X 240.77592 | 1685.43 | |
| 2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed | | | | | | | | |
| Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge. | | | | | | | | |
| SI No | Description | No | L | B | D | CF | Quantity | Deduction |
| i | Cut off | 2.000 | 70.000 | 0.250 | 0.050 | 1.000 | 1.750 | - |
| ii | Bed | 1.000 | 70.000 | 3.150 | 0.100 | 1.000 | 22.050 | - |
| Total Quantity | | | | | | 23.8 cum (cum) | 23.8 Cum (Cubic Meter) | |
| Amount | | | | | | 23.8 X 651.958232 | 15516.61 | |
| 3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal | | | | | | | | |
| Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. | | | | | | | | |
| SI No | Description | No | L | B | D | CF | Quantity | Deduction |
| i | cut off | 2.000 | 70.000 | 0.250 | 0.350 | 1.000 | 12.250 | - |
| ii | Bed | 1.000 | 70.000 | 3.150 | 0.100 | 1.000 | 22.050 | - |
| Total Quantity | | | | | | 34.3 cum (cum) | 34.3 Cum (Cubic Meter) | |

| Amount | | | | | | 34.3 X 5450.45165184 | 186950.49 | |
|---|-------------|-------|--------|-------|------------------------------------|-----------------------------|---------------------------|-----------|
| 4. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum | | | | | | | | |
| Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge. | | | | | | | | |
| SI No | Description | No | L | B | D | CF | Quantity | Deduction |
| i | Bed | 1.000 | 70.000 | 3.450 | 0.075 | 1.000 | 18.113 | - |
| Total Quantity | | | | | 18.1125 cum (cum) | | 18.1125 Cum (Cubic Meter) | |
| Amount | | | | | 18.1125 X 6907.54251808 | | 125112.86 | |

| |
|-------------------------------------|
| Total Amount (A) : 329265.39 |
|-------------------------------------|

| Additional Components | | | |
|---|---------------------------------|----------------------|-----------------|
| # | Item Name | Remark | Amount (in Rs.) |
| 1 | Provision for Contingency @ 1% | - | 3292.6539287844 |
| 2 | Display Citizen Board @ Rs.4000 | - | 4000 |
| 3 | Any Other Lumpsum @ Rs.3441 | Vibrator & Thermocol | 3441 |
| Additional Components Amount (F) : 10733.653928784 | | | |

| |
|---|
| Grand Total Amount (A + F) : 339999.04680722 |
|---|

JE
Dhenkanal Sadar Block

Ramratan Bhuyan
AEE
Dhenkanal Sadar Block

Rahul Mandal
BDO
Dhenkanal Sadar Block