

## Detailed Estimate

**OD/366/3521/120557/428018/00109017 : CONST OF CC DRAIN AT CHARAMULA RAM MANDIR TO PRIMARY SCHOOL**

**Block : Tentulikhunti, Gram Panchayat : Digi**

**Created By:UMAKANTA SAHANI**

<b>1. Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b>								
Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Drain	1.000	90.000	1.200	0.800	1.000	86.400	-
<b>Total Quantity</b>						86.4 cum (cum)	86.4 Cum (Cubic Meter)	
<b>Amount</b>						<b>86.4 X 240.77592</b>	<b>20803.04</b>	
<b>2. Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed</b>								
Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Drain	1.000	90.000	1.200	0.100	1.000	10.800	-
<b>Total Quantity</b>						10.8 cum (cum)	10.8 Cum (Cubic Meter)	
<b>Amount</b>						<b>10.8 X 535.707232</b>	<b>5785.64</b>	
<b>3. Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b>								
Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.								
SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Drain base	1.000	90.000	1.200	0.100	1.000	10.800	-
ii	Drain walls	2.000	90.000	0.300	0.600	1.000	32.400	-
<b>Total Quantity</b>						43.2 cum (cum)	43.2 Cum (Cubic Meter)	
<b>Amount</b>						<b>43.2 X 5217.6713928</b>	<b>225403.40</b>	

**4. R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc**

Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Drain walls	2.000	90.000	0.000	0.600	1.000	108.000	-
Total Quantity					108 Sqm (Sqm)		108 Sqm (Square Meter)	
Amount					108 X 216.23489289764		23353.37	

**5. Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum**

Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.

SI No	Description	No	L	B	D	CF	Quantity	Deduction
i	Drain base	1.000	90.000	0.600	0.025	1.000	1.350	-
ii	Drain wall	2.000	90.000	0.300	0.025	1.000	1.350	-
Total Quantity					2.7 cum (cum)		2.7 Cum (Cubic Meter)	
Amount					2.7 X 6744.7772326		18210.90	

**Total Amount (A) : 293556.35**

**Additional Components**

#	Item Name	Remark	Amount (in Rs.)
1	Display Citizen Board @ Rs.3443	-	3443
2	Provision for Contingency @ Rs.3000	-	3000

**Additional Components Amount (F) : 6443**

**Grand Total Amount (A + F) : 299999.34872353**

**UMAKANTA SAHANI**  
**JE**  
**Tentulikhunti Block**

**GOVIND KANHAR**  
**AEE**  
**Tentulikhunti Block**

**Manoj Kumar Panigrahi**  
**BDO**  
**Tentulikhunti Block**