

Measurements

OD/365/3497/120199/391128/00078873 : REPAIRING AND MAINTANANCE OF PODADIHA GOVT ME SCHOOL
Block : Kaptipada, Gram Panchayat : Jayantipata-Samil-Jamdiha
Created By:MANORANJAN SENAPATI

Measurement Book No : 35/25-26					Measurement Date : 2026-05-12			Pages : 52 to 58			
Item 1 : Painting						Spec. Code : AR0901d					
Spec Decription : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.											
S/N	Description	N	L	B	D	CF	Quantity	Remarks	Deduction	CM	TC
i	verandah	2	13.75		3.05		83.875			✓	
ii	colm	4	1.2		2.15		10.32				
iii	chajah	1	11.2975		1.08		12.2013				
iv	celling	1	10.79	2.88			31.0752			✓	
v		1	13.25	2			26.5				
vi	b.wall	1	181	2	1.75		633.5			✓	
vii	GCI build	2	30.34		3.03		183.8604				
viii	colm	10	1.2		2.3		27.6				
ix	gable	1	5.49		1.8		9.882				
x	parapet	2	5.65	0.85			9.605				
xi	build-3 o/s	2	15.09		3.6		108.648				
xii	vre colmt	3	1.2		2.1		7.56				
xiii	toilet	2	8.98		2.4		43.104				
xiv	ver open	1	16.55		2.1		34.755		34.755		
xv		1	11.82		2.1		24.822		24.822		
xvi	door	12	1.07		2		25.68		25.68		

xvii	d1	4	0.75		1.8		5.4		5.4		
xviii	window	16	1.2		1.2		23.04		23.04		
xix	main gate colm	2	2		3.7		14.8				
xx	gate beam	1	4.6		1.4		6.44				
xxi		4	7.66		3.5		107.24				
xxii	door	2	1.07		2		4.28		4.28		
xxiii	W	2	0.9		1.2		2.16		2.16		
Total Quantity							1196.0739 Sqm (1196.0739 Sqm)				
Amount							1196.0739 X 71.85266428151 = Rs. 85941.10				
Item 2 : Painting							Spec. Code : AR0920				
Spec Description : Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)											
S/N	Description	N	L	B	D	CF	Quantity	Remarks	Deduction	CM	TC
i	priming area	1196.07					1196.07				
ii	I/S room	4	11.77		3.05		143.594			✓	
iii	do	4	10.88		2.7		117.504			✓	
iv	celling	2	6.94	4.83			67.0404				
v		1	5.9	4.98			29.382				
Total Quantity							1553.5904 Sqm (1553.5904 Sqm)				
Amount							1553.5904 X 94.7826508375 = Rs. 147253.42				
Item 3 : Dismantling							Spec. Code : AR1618				

Spec Description :

Dismantling and removing doors, windows and ventilators including removal of frame, hinges, fastening and stacking the same for reuse and removing the debris within 50m and as per direction of Engineer-in-Charge.

Pre Measurement Date :

09-03-2026

S/N	Description	N	L	B	D	CF	Quantity	Remarks	Deduction	CM	TC
i	door	2	1.07	1.98			4.2372			✓	
ii	window	3	0.9	1.2			3.24				
Total Quantity							7.4772 Sqm (7.4772 Sqm)				
Amount							7.4772 X 396.30846153846 = Rs. 2963.28				

Item 4 : Iron Work

Spec. Code : AR1704

Spec Description :

Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.

S/N	Description	N	L	B	D	CF	Quantity	Remarks	Deduction	CM	TC
i	door	2	1.07	1.98		23	97.4556			✓	
ii	window	3	1.2	1.2		32	138.24				
Total Quantity							235.6956 Kg (2.356956 Qntl)				
Amount							2.356956 X 15771.744505087 = Rs. 37173.31				

Item 5 : Painting

Spec. Code : AR0901b

Spec Description :

Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

S/N	Description	N	L	B	D	CF	Quantity	Remarks	Deduction	CM	TC
i	door	2	1.07	1.98	2.25		9.5337			✓	
ii	window	3	1.2	1.2	2.75		11.88				

Total Quantity							21.4137 Sqm (21.4137 Sqm)				
Amount							21.4137 X 66.10221283871 = Rs. 1415.49				
Item 6 : Painting							Spec. Code : AR0903i				
Spec Decription : Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)											
S/N	Description	N	L	B	D	CF	Quantity	Remarks	Deduction	CM	TC
i	door	12	1.07		1.98	2.25	57.2022			✓	
ii	window	13	0.9		1.2	2.75	38.61				
iii	door	4	0.75		1.8	2.25	12.15				
iv	W	3	1.2	1.2		2.75	11.88				
Total Quantity							119.8422 Sqm (119.8422 Sqm)				
Amount							119.8422 X 164.25024333952 = Rs. 19684.11				
Item 7 : Other Building Items.							Spec. Code : AR1903				
Spec Decription : Providing fitting and fixing of false ceiling with Aluminium anodised T Section No.3215 with 2'-0" center to center, L section No.1705 upto 15 micron on 4 walls to be fixed by means of steel screw and P.V.C.plug and the Aluminium grid 2'-0"x2'-0"with 12mm thick Prelaminated Novapan board suspended from ceiling etc. complete and as per direction of engineer in charge.											
S/N	Description	N	L	B	D	CF	Quantity	Remarks	Deduction	CM	TC
i	c.room	1	7.53	4.88			36.7464			✓	
Total Quantity							36.7464 Sqm (36.7464 Sqm)				
Amount							36.7464 X 1438.4422086713 = Rs. 52857.57				
Total Amount							Rs. 347288.27453474				

Addition Component

i) Provision for PH Work	Rs. 10000
ii) Provision for EI Work	Rs. 30810
iii) Display Citizen Board	Rs. 3000
iv) Any Other Lumpsum	Rs. 7000
v) Contingency	Rs. 1900
Total Addition	Rs. 52710

Deduction Component

i) Contingency	Rs. 1900
ii) Labour Cess	Rs. 4000
iii) Any Other Lumpsum Bill	Rs. 10000
Total Deduction	Rs. 15900

Grand Total Amount : Rs. 384098.27453474