

ESTIMATION DPR							
State	Odisha	District	Sonepur	Block	Biramaharajpur	Gram Panchayat	Luthurpank

Work Code	OD/372/3568/121447/419459/00040570 (Construction of CC Road at Kulsahi village)						
Project Category	Road						

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Biramaharajpur	Proposal Date	10-12-2024
Date of Commencement	10-02-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	debabehera		

Administrative Approval Details

Approval No.	OD/372/3568/121447/419459/00040570/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/372/3568/121447/419459/00040570/TS
Fund Sanction No.	29143
Fund Sanction Amount (in Rs.)	143788

ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	Sqm	24.75	216.39264180804	424.997496
2	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	Cum	9.03375	7127.21854626	424.997496

3	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	11.34375	5711.39344798	424.997496
4	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	Cum	8.58	581.056232	424.997496

5	Earth Work (AR0102a1) : Earthwork in hard soil or gravelly soil within 50m to 75m lead and 1.5m, initial lift - Earthwork in hard soil or gravelly soil within 50m to 75m lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.	Cum	1.98	214.6452	424.997496
Total Amount (in Rs.): 139940.30781911					

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	24.75	Sqm
i	Semi-Skilled	0.05	1.2375	-
ii	Skilled	0.05	1.2375	-

2	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	9.03375	Cum
i	Un-Skilled	4.6	41.55525	-
ii	Skilled	0.68	6.14295	-
3	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	11.34375	Cum
i	Skilled	0.18	2.041875	-

	ii	Un-Skilled	3.9	44.240625	-
4		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	8.58	Cum
	i	Un-Skilled	0.1236	1.060488	-
5		Earth Work (AR0102a1) : Earthwork in hard soil or gravelly soil within 50m to 75m lead and 1.5m, initial lift - Earthwork in hard soil or gravelly soil within 50m to 75m lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.	-	1.98	Cum
	i	Un-Skilled	0.46	0.9108	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Semi-Skilled	1.2375	512	633.6
1	Skilled	9.422325	562	5295.34665
2	Un-Skilled	87.767163	462	40548.429306

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	24.75	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.0660825	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	3.1185	1Mtr.
2	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	9.03375	Cum
i)	BRM340 : Cement	3.23	29.1790125	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	4.0651875	1 Cum

iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	8.130375	1 Cum.
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	11.34375	Cum
i)	BRM340 : Cement	2.29	25.9771875	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	5.445	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	10.89	1 Cum.
4	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	8.58	Cum
i)	BRM029 : Sand for filling and road blinding	1	8.58	1 Cum

5	Earth Work (AR0102a1) :.Earthwork in hard soil or gravelly soil within 50m to 75m lead and 1.5m, initial lift - Earthwork in hard soil or gravelly soil within 50m to 75m lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.	-	1.98	Cum
---	--	---	------	-----

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM104	0.0660825	1Cum.	58620.646	3873.798839295
2	BRM092	3.1185	1Mtr.	276.666	862.782921
3	BRM340	55.1562	1 Qntl.	540.227	29796.8684574
4	BRM028	9.5101875	1 Cum	352.89	3356.050066875
5	BRM056	8.130375	1 Cum.	2241.91	18227.56901625
6	BRM044	10.89	1 Cum.	1857.16	20224.4724
7	BRM029	8.58	1 Cum	347.95	2985.411
Total: 79326.95270082					

ROYALTY STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	24.75	Sqm

i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.0660825	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000614	0.0151965	1Mtr.
2	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	9.03375	Cum
i)	BRM340 : Cement	3.23	29.1790125	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	4.0651875	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	8.130375	1 Cum.

3	<p>Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	11.34375	Cum
i)	BRM340 : Cement	2.29	25.9771875	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	5.445	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	10.89	1 Cum.
4	<p>Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	8.58	Cum
i)	BRM029 : Sand for filling and road blinding	1	8.58	1 Cum

5	Earth Work (AR0102a1) :.Earthwork in hard soil or gravelly soil within 50m to 75m lead and 1.5m, initial lift - Earthwork in hard soil or gravelly soil within 50m to 75m lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.	-	1.98	Cum
---	--	---	------	-----

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	BRM028	9.5101875	1 Cum	170.25	1619.109421875
2	BRM056	8.130375	1 Cum.	279.5	2272.4398125
3	BRM044	10.89	1 Cum.	279.5	3043.755
4	BRM029	8.58	1 Cum	170.25	1460.745
Total: 8396.049234375					

ADDITION COMPONENT

SI.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ Rs. 1438	Rs. 1438
2	Display Citizen Board @ Rs. 2400	Rs. 2400
Total Addition Component Amount (in Rs.): 3838		

Total Net Amount (in Rs.): 143778.30781911