

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Rayagada	<b>Block</b>	Muniguda	<b>Gram Panchayat</b>	Saradhapur

<b>Work Code</b>	OD/370/3554/121221/424749/00056749 (REPAIR AND MAINTANCE OF SARADHAPUR HIGH SCHOOL )
<b>Project Category</b>	Building

<b>Financial Year</b>	2023-24	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Muniguda	<b>Proposal Date</b>	-
<b>Date of Commencement</b>	11-11-2025	<b>Date of Completion</b>	17-02-2026
<b>Scheme Name</b>	Construction of Additional Class Room in Secondary Schools	<b>Scheme Component Name</b>	Self/Personal Deposit
<b>Project Sub-Category</b>	Secondary School	<b>Project Type</b>	Repair and Maintenance
<b>Name of Executant</b>	Sanjam Kumar Nayak		

### Administrative Approval Details

<b>Approval No.</b>	OD/370/3554/121221/424749/00056749/AS
---------------------	---------------------------------------

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/370/3554/121221/424749/00056749/TS
<b>Fund Sanction No.</b>	
<b>Fund Sanction Amount (in Rs.)</b>	120000

### LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<b>Dismantling (AR1621) : Removing old grading plaster from roof</b> - Removing old grading plaster from roof slab, cleaning the surface,lowering and removing the debris within 50m lead and as per direction of Engineer-in-Charge.	-	90.25	Sqm
i	Un-Skilled	0.166666666666667	15.0416666666667	-

2	<p><b>Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) -</b> Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&amp;P required for the work complete as per direction of the Engineer-in-charge.</p>	-	216	Sqm
i	Highly-Skilled	0.053763440860215	11.612903225806	-
ii	Un-Skilled	0.053763440860215	11.612903225806	-
3	<p><b>Painting (AR0922) : Finishing wall two coats with distemper of approved shades on new work (Inside) -</b> Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p>	-	216	Sqm
i	Highly-Skilled	0.052	11.232	-
ii	Un-Skilled	0.062	13.392	-

4	<b>Painting (AR0903i) : Painting two coats of enamel paint in outer surface paint (outer surface) -</b> Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	6.4	Sqm
i	Highly-Skilled	0.13440860215054	0.86021505376344	-
ii	Un-Skilled	0.11827956989247	0.75698924731183	-
5	<b>Plastering (AR1004) : First Floor -</b> 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	6	Sqm
i	Un-Skilled	0.1236	0.7416	-
ii	Skilled	0.1442	0.8652	-

6	<p><b>Concrete (AR0318) : 4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken) - 4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken) including hoisting and laying in position compacting and curing for the proper period with cost conveyance, royalty, taxes of all materials, labor and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge. (Old Work)</b></p>	-	90.25	Sqm
i	Un-Skilled	1.008	90.972	-
ii	Highly-Skilled	0.165	14.89125	-
7	<p><b>Dismantling (AR1612) : Dismantling and removing 2.5 cm. thick artificial stone flooring - Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.</b></p>	-	24	Sqm
i	Un-Skilled	0.21505376344086	5.1612903225806	-

8	<b>Flooring (AR0802i) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips</b> - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.	-	24	Sqm
i	Un-Skilled	0.36	8.64	-
ii	Highly-Skilled	0.13	3.12	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	146.31844946237	462	67599.123651613
1	Highly-Skilled	41.71636827957	612	25530.417387097
2	Skilled	0.8652	562	486.2424
<b>Total: 93615.78343871</b>				