

ESTIMATION DPR							
State	Odisha	District	Dhenkanal	Block	Kamakhyana gar	Gram Panchayat	Tumsinga

Work Code	OD/352/3353/117364/402840/00062268 (Construction of Patiagoda Sahi CC Road)
Project Category	Road

Financial Year	2020-21	Execution Level	PS
Executing Agency	Panchayat Samiti, Kamakhyanagar	Proposal Date	-
Date of Commencement	23-12-2025	Date of Completion	27-02-2026
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	SUSAMA BEHERA		

Administrative Approval Details

Approval No.	OD/352/3353/117364/402840/00062268/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/352/3353/117364/402840/00062268/TS
Fund Sanction No.	22117
Fund Sanction Amount (in Rs.)	500000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	53.35	Cum

	i	Un-Skilled	0.516	27.5286	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	33.55	Cum
	i	Un-Skilled	0.1236	4.14678	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	39.93	Cum
	i	Skilled	0.18	7.1874	-
	ii	Un-Skilled	3.9	155.727	-

4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	25.74	Cum
i	Un-Skilled	4.6	118.404	-
ii	Skilled	0.68	17.5032	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	305.80638	462	141282.54756
1	Skilled	24.6906	562	13876.1172
Total: 155158.66476				