

ESTIMATION DPR							
State	Odisha	District	Jagatsinghpur	Block	Naugaon	Gram Panchayat	Galadari

Work Code	OD/355/3391/118179/398106/00059321 (IMPROVEMENT OF CC ROAD FROM KUMBHAR SAHI TO KANGINI BARIK HOUSE, VIL- GALADARI)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Naugaon	Proposal Date	-
Date of Commencement	25-03-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	Upgradation or Improvement
Name of Executant	SONALI MALLICK		

Administrative Approval Details

Approval No.	OD/355/3391/118179/398106/00059321/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/355/3391/118179/398106/00059321/TS
Fund Sanction No.	1990
Fund Sanction Amount (in Rs.)	100000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	11.7425	Cum
i	Un-Skilled	4.6	54.0155	-
ii	Skilled	0.68	7.9849	-
2	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	7.6	Sqm
i	Semi-Skilled	0.05	0.38	-
ii	Skilled	0.05	0.38	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
--------	-------------	----------	------	--------

0	Un-Skilled	54.0155	462	24955.161
1	Skilled	8.3649	562	4701.0738
2	Semi-Skilled	0.38	512	194.56
				Total: 29850.7948