

ESTIMATION DPR							
State	Odisha	District	Mayurbhanj	Block	Jamda	Gram Panchayat	Bad Dundu

Work Code	OD/365/3495/120163/387514/00054885 (Const of CC road at Baddundu Muslim Kabarstan)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Jamda	Proposal Date	-
Date of Commencement	06-12-2025	Date of Completion	-
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	PRATAP SINGh		

Administrative Approval Details

Approval No.	OD/365/3495/120163/387514/00054885/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/365/3495/120163/387514/00054885/TS
Fund Sanction No.	14036
Fund Sanction Amount (in Rs.)	200000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	1.11	Cum

	i	Un-Skilled	0.516	0.57276	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	7.3075	Cum
	i	Un-Skilled	0.1236	0.903207	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	17.02	Cum
	i	Skilled	0.18	3.0636	-
	ii	Un-Skilled	3.9	66.378	-

4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	13.32	Cum
i	Un-Skilled	4.6	61.272	-
ii	Skilled	0.68	9.0576	-
5	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	38.85	Sqm
i	Semi-Skilled	0.05	1.9425	-
ii	Skilled	0.05	1.9425	-
SI.No.	Labour Type	Qty Unit	Rate	Amount

0	Un-Skilled	129.125967	462	59656.196754
1	Skilled	14.0637	562	7903.7994
2	Semi-Skilled	1.9425	512	994.56
				Total: 68554.556154