

ESTIMATION DPR							
State	Odisha	District	Ganjam	Block	Bellaguntha	Gram Panchayat	Benipalli

Work Code	OD/354/3366/117619/410678/00064174 (CONSTRUCTION OF PAVER C.C.ROAD FROM CHANDRASEKHAR TO UP SCHOOL)						
Project Category	Road						

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Bellaguntha	Proposal Date	-
Date of Commencement	17-11-2025	Date of Completion	09-01-2026
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	Pavor Block	Project Type	New Work
Name of Executant	Phulamani Majhi		

Administrative Approval Details

Approval No.	OD/354/3366/117619/410678/00064174/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/354/3366/117619/410678/00064174/TS
Fund Sanction No.	9122
Fund Sanction Amount (in Rs.)	250000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Meaurement Qty)	Unit
1	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	27.510337536	Cum
i	Un-Skilled	0.1236	3.4002777194496	-

2	Concrete (AR0307a) : Cement concrete (1:2:4)with 12mm size hard granite(Hand broken)chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(hand broken) chips including hoisting and laying in position compacting to proper thickness and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	3.6245504	Cum
i	Un-Skilled	4.6	16.67293184	-
ii	Skilled	0.68	2.464694272	-
3	miscellaneous (ARM287) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC - Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.	-	273.506432	Sqm

Sl.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	20.07320955945	462	9273.8228164657
1	Skilled	2.464694272	562	1385.158180864
				Total: 10658.98099733