

ESTIMATION DPR

State	Odisha	District	Puri	Block	Kanas	Gram Panchayat	Kadua
--------------	--------	-----------------	------	--------------	-------	-----------------------	-------

Work Code	OD/369/3541/120984/410114/00054993 (IMP. OF ROAD WITH CC/GR.II METALLING FROM BAJARANGI TEMPLE TO SANAORA UP SCHOOL)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Kanas	Proposal Date	-
Date of Commencement	24-09-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance and improvement of Road infrastructure
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	GOPINATH PALAI		

Administrative Approval Details

Approval No.	OD/369/3541/120984/410114/00054993/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/369/3541/120984/410114/00054993/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	186532

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	10.35	Cum
i	Skilled	0.18	1.863	-
ii	Un-Skilled	3.9	40.365	-
2	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	11.22	Sqm
i	Semi-Skilled	0.05	0.561	-
ii	Skilled	0.05	0.561	-

3	R.C.C. Work (AR0401) : R.C.C work - Reinforced cement concrete (1:2:4) work with 12mm size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (To be used for minor repair work only)	-	15.249	Cum
i	Un-Skilled	4.6	70.1454	-
ii	Skilled	0.68	10.36932	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Skilled	12.79332	562	7189.84584
1	Un-Skilled	110.5104	462	51055.8048
2	Semi-Skilled	0.561	512	287.232
Total:				58532.88264