

ESTIMATION DPR							
State	Odisha	District	Balasore	Block	Baleshwar	Gram Panchayat	Alumeda

Work Code	OD/346/3299/275539/392299/00013869 (Const. of CC road from Juari RD Road to Braja Mohan College, W No- 3 Vill:- Nuakundi, GP Alumeda)
Project Category	Road

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Baleshwar	Proposal Date	22-05-2023
Date of Commencement	07-04-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	MAINTENANCE OF ROADS AND BRIDGES
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	GAGANA BIHARI JENA		

Administrative Approval Details

Approval No.	OD/346/3299/275539/392299/00013869/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/346/3299/275539/392299/00013869/TS
Fund Sanction No.	4907
Fund Sanction Amount (in Rs.)	200000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0101aa) : Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift - Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge per 100 cum	-	2.8	Cum

	i	Un-Skilled	0.384	1.0752	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	10.15	Cum
	i	Un-Skilled	0.1236	1.25454	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	13.3	Cum
	i	Skilled	0.18	2.394	-
	ii	Un-Skilled	3.9	51.87	-

4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	10.5	Cum
i	Un-Skilled	4.6	48.3	-
ii	Skilled	0.68	7.14	-
5	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	28	Sqm
i	Semi-Skilled	0.05	1.4	-
ii	Skilled	0.05	1.4	-
SI.No.	Labour Type	Qty Unit	Rate	Amount

0	Un-Skilled	102.49974	462	47354.87988
1	Skilled	10.934	562	6144.908
2	Semi-Skilled	1.4	512	716.8
				Total: 54216.58788