

ESTIMATION DPR							
State	Odisha	District	Sambalpur	Block	Kuchinda	Gram Panchayat	Telitleimal

Work Code	OD/371/3562/121365/381575/00022880 (Const of Market Complex at Kaputikira, Telitleimal GP)
Project Category	Building

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Kuchinda	Proposal Date	-
Date of Commencement	20-03-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Creation of Capital Asset for Revenue Generation
Project Sub-Category	Market Complex	Project Type	New Work
Name of Executant	Prakash Kumar Ping		

Administrative Approval Details

Approval No.	OD/371/3562/121365/381575/00022880/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/371/3562/121365/381575/00022880/TS
Fund Sanction No.	32
Fund Sanction Amount (in Rs.)	1000000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	39.345	Cum

	i	Un-Skilled	0.516	20.30202	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	52.590475	Cum
	i	Un-Skilled	0.1236	6.50018271	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	12.11392	Cum
	i	Skilled	0.18	2.1805056	-
	ii	Un-Skilled	3.9	47.244288	-

4	Masonry Brick Work (AR0603c) : Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	35.621944	Cum
i	Un-Skilled	2.96	105.44095424	-
ii	Skilled	1.05	37.4030412	-
iii	Highly-Skilled	0.35	12.4676804	-

5	Masonry Brick Work (AR0603ci) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	20.29152	Cum
i	Un-Skilled	2.96	60.0628992	-
ii	Skilled	1.05	21.306096	-
iii	Highly-Skilled	0.35	7.102032	-

6	R.C.C. Work (AR0404B) : Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips.(Nominal mix as per IS-456, Table-9). - R.C.C. work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge(Nominal mix as per IS-456, Table-9).	-	24.050393	Cum
i	Un-Skilled	1.3333	32.0663889869	-
ii	Skilled	0.1	2.4050393	-
iii	Semi-Skilled	0.0573	1.3780875189	-

7	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	22.8475	Qntl
i	Un-Skilled	0.8	18.278	-
ii	Highly-Skilled	0.3	6.85425	-
iii	Semi-Skilled	0.044	1.00529	-
8	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	43.45702	Sqm
i	Semi-Skilled	0.05	2.172851	-

	ii	Skilled	0.05	2.172851	-
9		R.C.C. Work (AR0410d) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm	-	26.54614	Sqm
	i	Semi-Skilled	0.6547619047619	17.381401190476	-
	ii	Skilled	0.6547619047619	17.381401190476	-
10		R.C.C. Work (AR0410e) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm	-	20.0733	Sqm
	i	Semi-Skilled	0.16025641025641	3.216875	-
	ii	Skilled	0.16025641025641	3.216875	-

11	<p>R.C.C. Work (AR0410a) : Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height</p>	-	99.3273	Sqm	
	i	Semi-Skilled	0.305555555555556	30.3500083333333	-
	ii	Skilled	0.305555555555556	30.3500083333333	-
12	<p>Flooring (AR0817aa) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	9.765	Sqm	

	i	Highly-Skilled	0.325	3.173625	-
	ii	Un-Skilled	0.325	3.173625	-
	iii	Semi-Skilled	0.76	7.4214	-
13		Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)	-	54.3935	Sqm
	i	Un-Skilled	0.216	11.748996	-
	ii	Highly-Skilled	0.216	11.748996	-

14	<p>Other Building Items. (AR1902) : cement based wall putty (water based) - Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc. complete. and as per the direction of Engineer in Charge.</p>	-	201.7185	Sqm
i	Un-Skilled	0.057	11.4979545	-
ii	Skilled	0.05	10.085925	-
15	<p>Plastering (AR1004) : 12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.</p>	-	128.755	Sqm
i	Un-Skilled	0.12	15.4506	-
ii	Skilled	0.14	18.0257	-

16	<p>Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	-	118.833	Sqm
i	Un-Skilled	0.24	28.51992	-
ii	Skilled	0.16	19.01328	-
17	<p>Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.</p>	-	201.7185	Sqm
i	Highly-Skilled	0.053763440860215	10.845080645161	-
ii	Un-Skilled	0.053763440860215	10.845080645161	-

18	Painting (AR0901di) : Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces(outer surface) - Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	128.755	Sqm
i	Highly-Skilled	0.053763440860215	6.922311827957	-
ii	Un-Skilled	0.053763440860215	6.922311827957	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	378.05322111002	462	174660.58815283
1	Skilled	163.54072262381	562	91909.886114581
2	Highly-Skilled	59.113975873118	612	36177.753234348
3	Semi-Skilled	62.92591304271	512	32218.067477867
Total:				334966.29497963