

ESTIMATION DPR

State	Odisha	District	Kandhamal	Block	Kotagarh	Gram Panchayat	Durgapanga
--------------	--------	-----------------	-----------	--------------	----------	-----------------------	------------

Work Code	OD/359/3428/118946/417228/00050617 (Renovation of Bandapipili Rural Haat)
Project Category	Other Infrastructure

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Kotagarh	Proposal Date	-
Date of Commencement	-	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance of Capital Assets
Project Sub-Category	Rural Haat	Project Type	Renovation or Rejuvenation
Name of Executant			

Administrative Approval Details

Approval No.	OD/359/3428/118946/417228/00050617/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/359/3428/118946/417228/00050617/TS
Fund Sanction No.	33742
Fund Sanction Amount (in Rs.)	400000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
---------------	----------------------	--	----------------------------------	-------------

1	R.C.C. Work (AR0404Aa) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)	-	0.6348	Cum
i	Un-Skilled	1.3333	0.84637884	-
ii	Skilled	0.175	0.11109	-
iii	Semi-Skilled	0.1323	0.08398404	-

2	Roofing (AR1132) : Supplying, feeting & fixing of G.C.I. Sheet (0.30mm thick) in roof drilling hole in wind ties - Supplying, fitting & fixing of G.C.I. Sheet (0.30mm thick) in roof drilling hole in wind ties including fixing of ridges valleys wind ties etc. including cost of fitting, Labour and material etc. complete as per direction of Engineer-in-Charge	-	450	Sqm
i	Un-Skilled	0.21505376344086	96.774193548387	-
ii	Highly-Skilled	0.16129032258065	72.58064516129	-
3	Iron Work (AR1701) : Labour for hoisting joints, trusses and placing in position - Labour for hoisting joints, trusses and placing in position with all cost of labour and machinery and T & P required for the work etc. as per direction of Engineer-in-Charge.	-	117.358	Qntl
i	Un-Skilled	0.33464566929134	39.273346456693	-
ii	Semi-Skilled	1.9685039370079	231.01968503937	-

4	<p>Painting (AR0901a) : Priming one coat in inner surface with primer of approved quality over woodwork - Priming one coat in inner surface with primer of approved quality over woodwork including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.</p>	-	100	Sqm
i	Highly-Skilled	0.053763440860215	5.3763440860215	-
ii	Un-Skilled	0.053763440860215	5.3763440860215	-
5	<p>Painting (AR0918c) : Finishing wall with two coat water proofing cement paint including one coat cement wash on the outer surface of approved shade on new work (Outside) - Finishing wall with two coat water proofing cement paint including one coat cement wash on the outer surface of approved shade on new work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)</p>	-	100	Sqm
i	Un-Skilled	0.042752688172043	4.2752688172043	-
ii	Highly-Skilled	0.022	2.2	-

iii	Skilled	0.0080645161290323	0.80645161290323	-
-----	---------	--------------------	------------------	---

Sl.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	146.54553174831	462	67704.035667717
1	Skilled	0.91754161290323	562	515.65838645161
2	Semi-Skilled	231.10366907937	512	118325.07856864
3	Highly-Skilled	80.156989247312	612	49056.077419355
Total:				235600.85004216