

ESTIMATION DPR							
State	Odisha	District	Mayurbhanj	Block	Tiring	Gram Panchayat	Lupung

Work Code	OD/365/3511/120402/387467/00049371 (DEVELOPMENT OF RURAL HAAT AT LUPUNG)
Project Category	Building

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Tiring	Proposal Date	-
Date of Commencement	16-01-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Development of Rural Haat
Project Sub-Category	Market Complex	Project Type	Upgradation or Improvement
Name of Executant	PURUSOTTAM NAHAK		

Administrative Approval Details

Approval No.	OD/365/3511/120402/387467/00049371/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/365/3511/120402/387467/00049371/TS
Fund Sanction No.	31804
Fund Sanction Amount (in Rs.)	1000000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	38.454	Cum

	i	Un-Skilled	0.516	19.842264	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	34.758	Cum
	i	Un-Skilled	0.1236	4.2960888	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	18.894	Cum
	i	Skilled	0.18	3.40092	-
	ii	Un-Skilled	3.9	73.6866	-

4	<p>R.C.C. Work (AR0404A) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)</p>	-	41.624	Cum
i	Un-Skilled	1.3333	55.4972792	-
ii	Skilled	0.1	4.1624	-
iii	Semi-Skilled	0.0573	2.3850552	-
5	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	53.1	Sqm

	i	Semi-Skilled	0.05	2.655	-
	ii	Skilled	0.05	2.655	-
6		R.C.C. Work (AR0410d) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm	-	102.75	Sqm
	i	Semi-Skilled	0.6547619047619	67.276785714286	-
	ii	Skilled	0.6547619047619	67.276785714286	-
7		R.C.C. Work (AR0410a) : Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height	-	122.06	Sqm

	i	Semi-Skilled	0.305555555555556	37.2961111111111	-
	ii	Skilled	0.305555555555556	37.2961111111111	-
8		Masonry Brick Work (AR0603b) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	7.8	Cum
	i	Un-Skilled	2.96	23.088	-
	ii	Skilled	1.05	8.19	-
	iii	Highly-Skilled	0.35	2.73	-

9	<p>Masonry Brick Work (AR0603bi) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	2.5	Cum
i	Un-Skilled	2.96	7.4	-
ii	Skilled	1.05	2.625	-
iii	Highly-Skilled	0.35	0.875	-
10	<p>Flooring (AR0802i) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.</p>	-	96.75	Sqm
i	Un-Skilled	0.36	34.83	-
ii	Highly-Skilled	0.13	12.5775	-

11	<p>Plastering (AR1027) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p>	-	207.74	Sqm
	i Un-Skilled	0.17	35.3158	-
	ii Skilled	0.14	29.0836	-
12	<p>Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	-	21.5	Sqm
	i Un-Skilled	0.24	5.16	-
	ii Skilled	0.16	3.44	-

13	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	25	Qntl
i	Un-Skilled	0.8	20	-
ii	Highly-Skilled	0.3	7.5	-
iii	Semi-Skilled	0.044	1.1	-
14	<p>Plastering (AR1017) : 20mm thick cement Plaster in CM (1:4) over masonry work in inside. - 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	-	116.6	Sqm
i	Un-Skilled	0.24	27.984	-

	ii	Skilled	0.16	18.656	-
15		<p>Painting (AR0921k) : Finishing wall One Coat with distemper of approved shades on old work (Inside)(For repair and maintenance). - Finishing wall One Coat with distemper of approved shades on old work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)(For repair and maintenance).</p>	-	181.1	Sqm
	i	Un-Skilled	0.0408	7.38888	-
	ii	Highly-Skilled	0.03366	6.095826	-
16		<p>Painting (AR0918g) : Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work .(Outside) - Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)</p>	-	48.1	Sqm

i	Un-Skilled	0.11776344086022	5.6644215053763	-
ii	Highly-Skilled	0.10776344086022	5.1834215053763	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	320.15333350538	462	147910.84007948
1	Skilled	176.7858168254	562	99353.629055873
2	Semi-Skilled	110.7129520254	512	56685.031437003
3	Highly-Skilled	34.961747505376	612	21396.58947329
Total:				325346.09004565