

ESTIMATION DPR							
State	Odisha	District	Koraput	Block	Bandhugaon	Gram Panchayat	Kutrabeda

Work Code	OD/363/3466/119712/428720/00049748 (Construction of Paver Block Road from RD Road to High School Mahaguda)
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Bandhugaon	Proposal Date	20-11-2024
Date of Commencement	16-01-2026	Date of Completion	25-02-2026
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	MAINTENANCE OF ROADS AND BRIDGES
Project Sub-Category	Pavor Block	Project Type	New Work
Name of Executant	Manoj Kumar Sahoo		

Administrative Approval Details

Approval No.	OD/363/3466/119712/428720/00049748/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/363/3466/119712/428720/00049748/TS
Fund Sanction No.	29781
Fund Sanction Amount (in Rs.)	414700

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	67.1492	Cum

	i	Un-Skilled	0.516	34.6489872	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	32.4918	Cum
	i	Un-Skilled	0.1236	4.01598648	-
3		R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	162.08	Sqm
	i	Semi-Skilled	0.05	8.104	-
	ii	Skilled	0.05	8.104	-

4	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	18.6392	Cum
i	Un-Skilled	4.6	85.74032	-
ii	Skilled	0.68	12.674656	-
5	<p>miscellaneous (ARM287) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC - Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	-	277.0136	Sqm

Sl.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	124.40529368	462	57475.24568016
1	Semi-Skilled	8.104	512	4149.248
2	Skilled	20.778656	562	11677.604672
				Total: 73302.09835216