

ESTIMATION DPR							
State	Odisha	District	Sonepur	Block	Biramaharajpur	Gram Panchayat	Champamal

Work Code	OD/372/3568/275228/419414/00052526 (Provision of facility Center Champamal GP HQ)
Project Category	Building

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Biramaharajpur	Proposal Date	-
Date of Commencement	-	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Provision of Facilities at GP Head Quarter
Project Sub-Category	GP Facility Centre	Project Type	New Work
Name of Executant			

Administrative Approval Details

Approval No.	
---------------------	--

Technical Sanction Details

Technical Sanction No.	
Fund Sanction No.	33921
Fund Sanction Amount (in Rs.)	1000000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	21.657424	Cum

	i	Un-Skilled	0.516	11.175230784	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	32.61267096	Cum
	i	Un-Skilled	0.1236	4.030926130656	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	8.5701555616	Cum
	i	Skilled	0.18	1.542628001088	-
	ii	Un-Skilled	3.9	33.42360669024	-

4	R.C.C. Work (AR0404Aa) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)	-	5.5956824768	Cum
i	Un-Skilled	1.3333	7.4607234463174	-
ii	Skilled	0.175	0.97924443344	-
iii	Semi-Skilled	0.1323	0.74030879168064	-

5	R.C.C. Work (AR0404Ab) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	1.8583463284	Cum
i	Un-Skilled	1.3333	2.4777331596557	-
ii	Skilled	0.35	0.65042121494	-
iii	Semi-Skilled	0.3073	0.57106982671732	-

6	R.C.C. Work (AR0404Ac) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	4.3028747452	Cum
i	Un-Skilled	1.3333	5.7370228977752	-
ii	Skilled	5.33875	22.971972545936	-
iii	Semi-Skilled	5.29605	22.788239794316	-

7	R.C.C. Work (AR0404Ad) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	1.11948574	Cum
i	Un-Skilled	1.3333	1.492610337142	-
ii	Skilled	2.34375	2.623794703125	-
iii	Semi-Skilled	2.30105	2.575992662027	-

8	R.C.C. Work (AR0404Ag) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	7.7943462668	Cum
i	Un-Skilled	1.3333	10.392201877524	-
ii	Skilled	3.15525	24.593111058321	-
iii	Semi-Skilled	3.11255	24.260292472728	-

9	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	18	Qntl
i	Un-Skilled	0.8	14.4	-
ii	Highly-Skilled	0.3	5.4	-
iii	Semi-Skilled	0.044	0.792	-
10	<p>Masonry Brick Work (AR0603c) : Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	12.5806235	Cum

	i	Un-Skilled	2.96	37.23864556	-
	ii	Skilled	1.05	13.209654675	-
	iii	Highly-Skilled	0.35	4.403218225	-
11		<p>Masonry Brick Work (AR0603ci) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	17.28696444	Cum
	i	Un-Skilled	2.96	51.1694147424	-
	ii	Skilled	1.05	18.151312662	-
	iii	Highly-Skilled	0.35	6.050437554	-

12	<p>Plastering (AR1027) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p>	-	61.5927	Sqm
i	Un-Skilled	0.17	10.470759	-
ii	Skilled	0.14	8.622978	-
13	<p>Plastering (AR1004) : 12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.</p>	-	109.598775	Sqm
i	Un-Skilled	0.12	13.151853	-
ii	Skilled	0.14	15.3438285	-

14	<p>Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	-	80.521075	Sqm
i	Un-Skilled	0.24	19.325058	-
ii	Skilled	0.16	12.883372	-
15	<p>Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in- charge(for new work only)</p>	-	49.00475	Sqm
i	Un-Skilled	0.216	10.585026	-
ii	Highly-Skilled	0.216	10.585026	-

16	<p>Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.</p>	-	230.51864	Sqm
i	Highly-Skilled	0.053763440860215	12.393475268817	-
ii	Un-Skilled	0.053763440860215	12.393475268817	-
17	<p>Painting (AR0920) : Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside) - Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p>	-	114.11836	Sqm
i	Highly-Skilled	0.054	6.16239144	-
ii	Un-Skilled	0.064	7.30357504	-

18	Painting (AR0918Ai) : Finishing wall one coat with weather coat - Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.	-	116.40028	Sqm
i	Un-Skilled	0.043	5.00521204	-
ii	Highly-Skilled	0.036	4.19041008	-
19	Painting (AR0903b) : Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.	-	18.6729	Sqm
i	Highly-Skilled	0.18817204301075	3.5137177419355	-
ii	Un-Skilled	0.17204301075269	3.2125419354839	-

20	Iron Work (AR1704) : Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in- charge.	-	3.36675	Qntl
i	Un-Skilled	6.3976377952756	21.539247047244	-
ii	Semi-Skilled	1.9685039370079	6.6274606299213	-
iii	Skilled	3.9370078740157	13.254921259843	-
iv	Highly-Skilled	3.4448818897638	11.598056102362	-
21	Other Building Items. (AR1902) : cement based wall putty (water based) - Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc.co mplete. and as per the direction of Engineer in Charge.	-	114.12	Sqm
i	Un-Skilled	0.057	6.50484	-
ii	Skilled	0.05	5.706	-

22	<p>Flooring (AR0817b) : Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) - Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	23.55015	Sqm
i	Un-Skilled	0.325	7.65379875	-
ii	Highly-Skilled	0.325	7.65379875	-

23	<p>miscellaneous (ARM297) : Supplying, fitting and fixing of two track UPVC sliding window of approved make with 6mm thick glass of approved quality complete with frame, shutters and all fitting and fixtures. (New miscellaneous items) and as directed by Engineer-in-Charge. - Supplying, fitting and fixing of two track UPVC sliding window of approved make with 6mm thick glass of approved quality complete with frame, shutters and all fitting and fixtures. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	-	4.4592	Sqm
24	<p>miscellaneous (ARM298) : Supplying, fitting and fixing of openable UPVC doors with door frame of approved make with 6mm thick glass. - Supplying, fitting and fixing of openable UPVC doors with door frame of approved make with 6mm thick glass of approved quality complete with frame, shutters and all fitting and fixtures. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	-	4.87725	Sqm

25	<p>Flooring (AR0816) : Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	7.0604	Sqm
	i Un-Skilled	0.216	1.5250464	-
	ii Highly-Skilled	0.216	1.5250464	-
	iii Semi-Skilled	0.55	3.88322	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	297.66854810726	462	137522.86922555
1	Skilled	140.53323905369	562	78979.680348175
2	Semi-Skilled	62.238584177391	512	31866.155098824
3	Highly-Skilled	73.475577562115	612	44967.053468014

