

ESTIMATION DPR							
State	Odisha	District	Mayurbhanj	Block	Kaptipada	Gram Panchayat	Pingu

Work Code	OD/365/3497/120211/391154/00048985 (Improvement of road with Paver Block road from Samal house to Panda house (CR-A/02/25-26))						
Project Category	Road						

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Kaptipada	Proposal Date	-
Date of Commencement	24-11-2025	Date of Completion	-
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	Pavor Block	Project Type	Upgradation or Improvement
Name of Executant	BIKASH KUMAR PARIDA		

Administrative Approval Details

Approval No.	OD/365/3497/120211/391154/00048985/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/365/3497/120211/391154/00048985/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	250000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p>miscellaneous (ARM287) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC -</p> <p>Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	-	10.95	Sqm
2	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</p> <p>Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	55	Sqm
i	Semi-Skilled	0.05	2.75	-
ii	Skilled	0.05	2.75	-

3	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	25.7049998175	Cum
i	Un-Skilled	4.6	118.2429991605	-
ii	Skilled	0.68	17.4793998759	-
4	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	4.5	Cum
i	Un-Skilled	0.516	2.322	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Semi-Skilled	2.75	512	1408

1	Skilled	20.2293998759	562	11368.922730256
2	Un-Skilled	120.5649991605	462	55701.029612151
				Total: 68477.952342407