

ESTIMATION DPR							
State	Odisha	District	Puri	Block	Kanas	Gram Panchayat	Badal

Work Code	OD/369/3541/120970/410112/00044299 (CONST. OF CC ROAD BFROM GANGADHARPUR SCHOOL TO LAXMIDHAR BEHERA HOUSE)
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Kanas	Proposal Date	-
Date of Commencement	31-07-2025	Date of Completion	-
Scheme Name	SFC Devolution of Fund	Scheme Component Name	5TH SFC DEVOLUTION GRANT TO PANCHAYAT SAMITI
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	UDAYABHANU MOHANTY		

Administrative Approval Details

Approval No.	OD/369/3541/120970/410112/00044299/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/369/3541/120970/410112/00044299/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	170000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Meaurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	2.2275	Cum

	i	Un-Skilled	0.516	1.14939	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	6.6	Cum
	i	Un-Skilled	0.1236	0.81576	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	14.751	Cum
	i	Skilled	0.18	2.65518	-
	ii	Un-Skilled	3.9	57.5289	-

4	Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	9.9	Cum
i	Un-Skilled	4.6	45.54	-
ii	Skilled	0.68	6.732	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	105.03405	462	48525.7311
1	Skilled	9.38718	562	5275.59516
Total: 53801.32626				