

ESTIMATION DPR							
State	Odisha	District	Sonepur	Block	Biramaharajpur	Gram Panchayat	Luthurpank

Work Code	OD/372/3568/121447/419459/00040570 (Construction of CC Road at Kulsahi village)
Project Category	Road

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Biramaharajpur	Proposal Date	10-12-2024
Date of Commencement	10-02-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	All Weather Connectivity
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	debabehera		

Administrative Approval Details

Approval No.	OD/372/3568/121447/419459/00040570/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/372/3568/121447/419459/00040570/TS
Fund Sanction No.	29143
Fund Sanction Amount (in Rs.)	143788

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	24.75	Sqm

	i	Semi-Skilled	0.05	1.2375	-
	ii	Skilled	0.05	1.2375	-
2		<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	9.03375	Cum
	i	Un-Skilled	4.6	41.55525	-
	ii	Skilled	0.68	6.14295	-
3		<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	11.34375	Cum

	i	Skilled	0.18	2.041875	-
	ii	Un-Skilled	3.9	44.240625	-
4		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	8.58	Cum
	i	Un-Skilled	0.1236	1.060488	-
5		Earth Work (AR0102a1) : Earthwork in hard soil or gravelly soil within 50m to 75m lead and 1.5m, initial lift - Earthwork in hard soil or gravelly soil within 50m to 75m lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.	-	1.98	Cum
	i	Un-Skilled	0.46	0.9108	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Semi-Skilled	1.2375	512	633.6
1	Skilled	9.422325	562	5295.34665

2	Un-Skilled	87.767163	462	40548.429306
				Total: 46477.375956