

ESTIMATION DPR							
State	Odisha	District	Mayurbhanj	Block	Udala	Gram Panchayat	Kundabai

Work Code	OD/365/3512/120414/390995/00049072 (Repair and maintenance of Kundabai Hata)
Project Category	Other Infrastructure

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Udala	Proposal Date	-
Date of Commencement	17-11-2025	Date of Completion	13-01-2026
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance of Capital Assets
Project Sub-Category	Rural Haat	Project Type	Repair and Maintenance
Name of Executant	UGRASEN MALLIK		

Administrative Approval Details

Approval No.	OD/365/3512/120414/390995/00049072/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/365/3512/120414/390995/00049072/TS
Fund Sanction No.	26956
Fund Sanction Amount (in Rs.)	240000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift -</p> <p>Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	14.4982016	Cum

	i	Un-Skilled	0.516	7.4810720256	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	20.954432	Cum
	i	Un-Skilled	0.1236	2.5899677952	-
3		Plastering (AR1027) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	-	81.197222	Sqm
	i	Un-Skilled	0.17	13.80352774	-
	ii	Skilled	0.14	11.36761108	-

4	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	53.512128	Sqm
i	Semi-Skilled	0.05	2.6756064	-
ii	Skilled	0.05	2.6756064	-
5	<p>Concrete (AR0303a) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	23.460610384	Cum
i	Un-Skilled	3.9	91.4963804976	-
ii	Skilled	0.18	4.22290986912	-

6	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	3.89356	Cum
i	Un-Skilled	4.6	17.910376	-
ii	Skilled	0.68	2.6476208	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	133.2813240584	462	61575.971714981
1	Skilled	20.91374814912	562	11753.526459805
2	Semi-Skilled	2.6756064	512	1369.9104768
Total: 74699.408651586				