

ESTIMATION DPR							
State	Odisha	District	Cuttack	Block	Cuttacksadar	Gram Panchayat	Jharkata

Work Code	OD/350/3337/275413/400054/00065505 (IMPROVEMENT OF ROAD FROM JHINKIRIA CHANDULI MAIN ROAD TO GOBINDAPUR VILLAGE ROAD)						
Project Category	Road						

Financial Year	2021-22	Execution Level	PS
Executing Agency	Panchayat Samiti, Cuttacksadar	Proposal Date	-
Date of Commencement	25-11-2025	Date of Completion	05-12-2025
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	MAINTENANCE OF ROADS AND BRIDGES
Project Sub-Category	CC Road	Project Type	Repair and Maintenance
Name of Executant	SAMAPEEKA NAYAK		

Administrative Approval Details

Approval No.	OD/350/3337/275413/400054/00065505/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/350/3337/275413/400054/00065505/TS
Fund Sanction No.	19514
Fund Sanction Amount (in Rs.)	200000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	2.6654320672	Cum

	i	Un-Skilled	0.516	1.3753629466752	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	12.666977930112	Cum
	i	Un-Skilled	0.1236	1.5656384721618	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	15.348402589715	Cum
	i	Skilled	0.18	2.7627124661487	-
	ii	Un-Skilled	3.9	59.858770099889	-

4	Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	12.671201664	Cum
i	Un-Skilled	4.6	58.2875276544	-
ii	Skilled	0.68	8.61641713152	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	121.08729917313	462	55942.332217984
1	Skilled	11.379129597669	562	6395.0708338898
Total: 62337.403051874				