

ESTIMATION DPR							
State	Odisha	District	Malkangiri	Block	Korukonda	Gram Panchayat	Korukonda

Work Code	OD/364/3482/119969/430305/00046756 (Construction of Guard wall at Mauliguda under CMSA for the year 24-25)
Project Category	CD Work

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Korukonda	Proposal Date	06-03-2025
Date of Commencement	08-08-2025	Date of Completion	11-08-2025
Scheme Name	Chief Minister Special Assistant	Scheme Component Name	Special Problem Fund (SPF) 16 th Phase
Project Sub-Category	Slab Culvert	Project Type	New Work
Name of Executant	BAPUJI NAYAK		

Administrative Approval Details

Approval No.	OD/364/3482/119969/430305/00046756/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/364/3482/119969/430305/00046756/TS
Fund Sanction No.	1363
Fund Sanction Amount (in Rs.)	200000

LABOUR STATEMENT

Sl.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102a3) : Earthwork in hard soil or gravelly soil within 100m to 125m lead and 1.5m, initial lift - Earthwork in hard soil or gravelly soil within 100m to 125m lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.	-	17.64	Cum

	i	Un-Skilled	0.535	9.4374	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	1.47	Cum
	i	Un-Skilled	0.1236	0.181692	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	29.89	Cum
	i	Skilled	0.18	5.3802	-
	ii	Un-Skilled	3.9	116.571	-

4	Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	0.98	Cum
i	Un-Skilled	4.6	4.508	-
ii	Skilled	0.68	0.6664	-
5	R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	98	Sqm
i	Semi-Skilled	0.05	4.9	-
ii	Skilled	0.05	4.9	-

Sl.No.	Labour Type	Qty Unit	Rate	Amount
--------	-------------	----------	------	--------

0	Un-Skilled	130.698092	462	60382.518504
1	Skilled	10.9466	562	6151.9892
2	Semi-Skilled	4.9	512	2508.8
				Total: 69043.307704