

ESTIMATION DPR							
State	Odisha	District	Rayagada	Block	Chandrapur	Gram Panchayat	Sarikima

Work Code	OD/370/3548/275313/425077/00063088 (IMPROVEMENT/MAINTENANCE OF MANDAP AT SARIKIMA)
Project Category	Building

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Chandrapur	Proposal Date	23-06-2023
Date of Commencement	24-02-2026	Date of Completion	23-03-2026
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance of Capital Assets
Project Sub-Category	Kalyan Mandap	Project Type	Repair and Maintenance
Name of Executant	ARUN SAHU		

Administrative Approval Details

Approval No.	OD/370/3548/275313/425077/00063088/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/370/3548/275313/425077/00063088/TS
Fund Sanction No.	11967
Fund Sanction Amount (in Rs.)	300000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	11.448	Cum

	i	Un-Skilled	0.516	5.907168	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	31.3985	Cum
	i	Un-Skilled	0.1236	3.8808546	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	29.3534	Cum
	i	Skilled	0.18	5.283612	-
	ii	Un-Skilled	3.9	114.47826	-

4	<p>Masonry Brick Work (AR0603c) : Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	1.404	Cum
i	Un-Skilled	2.96	4.15584	-
ii	Skilled	1.05	1.4742	-
iii	Highly-Skilled	0.35	0.4914	-
5	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	67.16	Sqm

	i	Semi-Skilled	0.05	3.358	-
	ii	Skilled	0.05	3.358	-
6		Plastering (AR1014ik) : 16mm thick cement Plaster in CM (1:6) over brick work in outside (Outside)(For repair and maintenance). - 16mm thick cement Plaster in CM (1:6) over brick work in outside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp. and as per direction of Engineer-in-charge(For repair and maintenance).	-	27.124	Sqm
	i	Un-Skilled	0.2448	6.6399552	-
	ii	Skilled	0.1632	4.4266368	-

7	<p>Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)</p>	-	62.41	Sqm
i	Un-Skilled	0.216	13.48056	-
ii	Highly-Skilled	0.216	13.48056	-
8	<p>Flooring (AR0802ii) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.</p>	-	4.68	Sqm
i	Un-Skilled	0.36	1.6848	-
ii	Highly-Skilled	0.13	0.6084	-

9	Painting (AR0922) : Finishing wall two coats with distemper of approved shades on new work (Inside) - Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	27.12	Sqm
i	Highly-Skilled	0.052	1.41024	-
ii	Un-Skilled	0.062	1.68144	-
10	Plastering (AR1033) : White washing two coats with stone lime in any surface - White washing two coats with stone lime in any surface including all costs of labour, coaltar and brushes required for the work etc. complete and as per direction of Engineer-in-charge.	-	27.12	Sqm
i	Un-Skilled	0.0080645161290323	0.21870967741935	-
ii	Skilled	0.010752688172043	0.29161290322581	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	152.12758747742	462	70282.945414568
1	Skilled	14.834061703226	562	8336.7426772129
2	Highly-Skilled	15.9906	612	9786.2472

3	Semi-Skilled	3.358	512	1719.296
				Total: 90125.231291781