

ESTIMATION DPR							
State	Odisha	District	Balangir	Block	Agalpur	Gram Panchayat	Nagaon(A)

Work Code	OD/345/3284/115769/419815/00035132 (Maintainance of Govt. Primary School Building at Mudapali Nagoan-A GP)						
Project Category	Building						

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Agalpur	Proposal Date	-
Date of Commencement	22-03-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance of Primary School Building
Project Sub-Category	Elementary School	Project Type	Repair and Maintenance
Name of Executant	Kirtiman Mohanty		

Administrative Approval Details

Approval No.	OD/345/3284/115769/419815/00035132/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/345/3284/115769/419815/00035132/TS
Fund Sanction No.	34989
Fund Sanction Amount (in Rs.)	300000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
--------	---------------	---	---------------------------	------

1	<p>Flooring (AR0816) : Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in- charge.</p>	-	57.878569	Sqm
i	Un-Skilled	0.216	12.501770904	-
ii	Highly-Skilled	0.216	12.501770904	-
iii	Semi-Skilled	0.55	31.83321295	-

2	<p>Flooring (AR0817b) : Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) - Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.</p>	-	3.384642096	Sqm
i	Un-Skilled	0.325	1.1000086812	-
ii	Highly-Skilled	0.325	1.1000086812	-

3	<p>Painting (AR0920a) : Finishing wall surface with two coats with plastic emulsion paint of approved shades above one coat oil bound Primer on new work (Inside) - Finishing wall surface with two coats with plastic emulsion paint of approved shades above one coat oil bound Primer on new work to give an even shade including all costs of labor, Paint, Primer, Brushes and putty required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p>	-	152.639629	Sqm
i	Highly-Skilled	0.10776344086022	16.448971632667	-
ii	Un-Skilled	0.11776344086022	17.975367922667	-
4	<p>Painting (AR0918g) : Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work .(Outside) - Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)</p>	-	108.324898	Sqm
i	Un-Skilled	0.11776344086022	12.756712719312	-

	ii	Highly-Skilled	0.10776344086022	11.673463739312	-
5		Painting (AR0903b) : Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.	-	14.876092875	Sqm
	i	Highly-Skilled	0.18817204301075	2.7992647883065	-
	ii	Un-Skilled	0.17204301075269	2.5593278064516	-
6		Other Building Items. (AR1902) : cement based wall putty (water based) - Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc.complete. and as per the direction of Engineer in Charge.	-	99.313307	Sqm
	i	Un-Skilled	0.057	5.660858499	-
	ii	Skilled	0.05	4.96566535	-

7	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	2.229948	Cum
i	Un-Skilled	0.516	1.150653168	-
8	<p>Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	5.946528	Cum
i	Un-Skilled	0.1236	0.7349908608	-

9	<p>Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	9.09818784	Cum
i	Skilled	0.18	1.6376738112	-
ii	Un-Skilled	3.9	35.482932576	-
10	<p>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</p>	-	7.84941696	Cum
i	Un-Skilled	4.6	36.107318016	-
ii	Skilled	0.68	5.3376035328	-

11	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	9.754815	Sqm
i	Semi-Skilled	0.05	0.48774075	-
ii	Skilled	0.05	0.48774075	-
12	<p>Masonry Brick Work (AR0603b) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	7.8791496	Cum
i	Un-Skilled	2.96	23.322282816	-

	ii	Skilled	1.05	8.27310708	-
	iii	Highly-Skilled	0.35	2.75770236	-
13		Plastering (AR1004) : 12mm thick cement plster (1:6) over Brick work in inside - 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	58.993405	Sqm
	i	Un-Skilled	0.12	7.0792086	-
	ii	Skilled	0.14	8.2590767	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	156.43143256943	462	72271.321847077
1	Highly-Skilled	47.281182105485	612	28936.083448557
2	Semi-Skilled	32.3209537	512	16548.3282944
3	Skilled	28.960867224	562	16276.007379888
Total:				134031.74096992