

ESTIMATION DPR							
State	Odisha	District	Sundargarh	Block	Subdega	Gram Panchayat	Damkuda

Work Code	OD/373/3587/121740/384060/00097284 (Construction of Market complex at Damkuda)
Project Category	Building

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Subdega	Proposal Date	-
Date of Commencement	09-03-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Creation of Capital Asset for Revenue Generation
Project Sub-Category	Market Complex	Project Type	New Work
Name of Executant	JAYA KUMAR KISAN		

Administrative Approval Details

Approval No.	OD/373/3587/121740/384060/00097284/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/373/3587/121740/384060/00097284/TS
Fund Sanction No.	
Fund Sanction Amount (in Rs.)	1000000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	29.7945	Cum

	i	Un-Skilled	0.516	15.373962	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	18.3162	Cum
	i	Un-Skilled	0.1236	2.26388232	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	9.63588	Cum
	i	Skilled	0.18	1.7344584	-
	ii	Un-Skilled	3.9	37.579932	-

4	Masonry Brick Work (AR0603c) : Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	8.9181275	Cum
i	Un-Skilled	2.96	26.3976574	-
ii	Skilled	1.05	9.364033875	-
iii	Highly-Skilled	0.35	3.121344625	-

5	<p>Masonry Brick Work (AR0603ci) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	19.611755	Cum
i	Un-Skilled	2.96	58.0507948	-
ii	Skilled	1.05	20.59234275	-
iii	Highly-Skilled	0.35	6.86411425	-
6	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	31.104	Sqm

	i	Semi-Skilled	0.05	1.5552	-
	ii	Skilled	0.05	1.5552	-
7		R.C.C. Work (AR0410d) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm	-	46.401	Sqm
	i	Semi-Skilled	0.6547619047619	30.381607142857	-
	ii	Skilled	0.6547619047619	30.381607142857	-
8		R.C.C. Work (AR0410e) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm	-	16.995	Sqm
	i	Semi-Skilled	0.16025641025641	2.7235576923077	-

	ii	Skilled	0.16025641025641	2.7235576923077	-
9		R.C.C. Work (AR0410a) : Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height	-	71.3875	Sqm
	i	Semi-Skilled	0.30555555555556	21.812847222222	-
	ii	Skilled	0.30555555555556	21.812847222222	-

10	R.C.C. Work (AR0404A) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	22.5182125	Cum
i	Un-Skilled	1.3333	30.02353272625	-
ii	Skilled	0.1	2.25182125	-
iii	Semi-Skilled	0.0573	1.29029357625	-

11	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	22.52	Qntl
i	Un-Skilled	0.8	18.016	-
ii	Highly-Skilled	0.3	6.756	-
iii	Semi-Skilled	0.044	0.99088	-
12	<p>Plastering (AR1027) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.</p>	-	60.845	Sqm
i	Un-Skilled	0.17	10.34365	-

	ii	Skilled	0.14	8.5183	-
13		Plastering (AR1004) : 12mm thick cement plster (1:6) over Brick work in inside - 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	55.2125	Sqm
	i	Un-Skilled	0.12	6.6255	-
	ii	Skilled	0.14	7.72975	-
14		Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	154.2075	Sqm
	i	Un-Skilled	0.24	37.0098	-
	ii	Skilled	0.16	24.6732	-

15	<p>Other Building Items. (AR1901Ba) : Vitrified Tile 600mmx600mm Coloured /Printed - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Coloured /Printed series(Homogeneous) in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all work all materials, taxes, labor, T&P , etc. complete as per direction of Engineer-in-charge.</p>	-	50.6525	Sqm
i	Un-Skilled	0.216	10.94094	-
ii	Highly-Skilled	0.216	10.94094	-

16	<p>Flooring (AR0817ab) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm Coloured /Printed series(Homogeneous) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm Coloured /Printed series(Homogeneous) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	4.87	Sqm
i	Highly-Skilled	0.325	1.58275	-
ii	Un-Skilled	0.325	1.58275	-
iii	Semi-Skilled	0.76	3.7012	-

17	<p>Other Building Items. (AR1902) : cement based wall putty (water based) - Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc. complete. and as per the direction of Engineer in Charge.</p>	-	214.405	Sqm
i	Un-Skilled	0.057	12.221085	-
ii	Skilled	0.05	10.72025	-
18	<p>Painting (AR0920b) : Finishing wall surface with two coats with plastic emulsion paint of approved shades above one coat waterbound Primer on new work (Inside) - Finishing wall surface with two coats with plastic emulsion paint of approved shades above one coat waterbound Primer on new work to give an even shade including all costs of labor, Paint, Primer, Brushes and putty required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)</p>	-	214.405	Sqm
i	Highly-Skilled	0.10776344086022	23.105020537634	-
ii	Un-Skilled	0.11776344086022	25.249070537634	-

19	Painting (AR0918cb) : Finishing wall two coats with weather coat with one coat waterbound Primer - Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	101.76	Sqm
i	Un-Skilled	0.11776344086022	11.983607741935	-
ii	Highly-Skilled	0.10776344086022	10.966007741935	-
20	Iron Work (AR1704) : Iron Doors and windows fixing - Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.	-	7.396	Qntl
i	Un-Skilled	6.3976377952756	47.316929133858	-
ii	Semi-Skilled	1.9685039370079	14.55905511811	-
iii	Skilled	3.9370078740157	29.11811023622	-
iv	Highly-Skilled	3.4448818897638	25.478346456693	-

21	Painting (AR0903b) : Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.	-	41.6025	Sqm
i	Highly-Skilled	0.18817204301075	7.8284274193548	-
ii	Un-Skilled	0.17204301075269	7.1574193548387	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	358.13651301452	462	165459.06901271
1	Skilled	171.17547856861	562	96200.618955557
2	Highly-Skilled	96.642951030618	612	59145.486030738
3	Semi-Skilled	77.014640751747	512	39431.496064895
Total:				360236.6700639