

ESTIMATION DPR							
State	Odisha	District	Kandhamal	Block	Raikia	Gram Panchayat	Dadingia

Work Code	OD/359/3431/118988/417546/00022672 (Construction of Market Complex at Dadaingia GP)
Project Category	Building

Financial Year	2024-25	Execution Level	PS
Executing Agency	Panchayat Samiti, Raikia	Proposal Date	-
Date of Commencement	17-09-2025	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Creation of Capital Asset for Revenue Generation
Project Sub-Category	Market Complex	Project Type	New Work
Name of Executant	MR SUBHENDU KUMAR PRADHAN		

Administrative Approval Details

Approval No.	OD/359/3431/118988/417546/00022672/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/359/3431/118988/417546/00022672/TS
Fund Sanction No.	202468692967
Fund Sanction Amount (in Rs.)	1000000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	42.6309424	Cum

	i	Un-Skilled	0.516	21.9975662784	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	40.5354992	Cum
	i	Un-Skilled	0.1236	5.01018770112	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	12.6301706208	Cum
	i	Skilled	0.18	2.273430711744	-
	ii	Un-Skilled	3.9	49.25766542112	-

4	R.C.C. Work (AR0404Aa) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)	-	6.796032	Cum
i	Un-Skilled	1.3333	9.0611494656	-
ii	Skilled	0.175	1.1893056	-
iii	Semi-Skilled	0.1323	0.8991150336	-

5	R.C.C. Work (AR0404Ab) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)	-	2.036342923552	Cum
i	Un-Skilled	1.3333	2.7150560199719	-
ii	Skilled	0.35	0.7127200232432	-
iii	Semi-Skilled	0.3073	0.62576818040753	-

6	R.C.C. Work (AR0404Ac) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)	-	5.9732096747008	Cum
i	Un-Skilled	1.3333	7.9640804592786	-
ii	Skilled	5.33875	31.889473150809	-
iii	Semi-Skilled	5.29605	31.634417097699	-

7	R.C.C. Work (AR0404Ad) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)	-	1.7627208	Cum
i	Un-Skilled	1.3333	2.35023564264	-
ii	Skilled	2.34375	4.131376875	-
iii	Semi-Skilled	2.30105	4.05610869684	-

8	R.C.C. Work (AR0404Ag) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)	-	10.3897737216	Cum
i	Un-Skilled	1.3333	13.852685303009	-
ii	Skilled	3.15525	32.782333535078	-
iii	Semi-Skilled	3.11255	32.338690197166	-

9	<p>Concrete (AR0317) : 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips - 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips including hoisting and laying in position compacting and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge. (new work)</p>	-	81.940446	Sqm
i	Un-Skilled	0.36	29.49856056	-
ii	Highly-Skilled	0.1	8.1940446	-
10	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	14	Qntl
i	Un-Skilled	0.8	11.2	-
ii	Highly-Skilled	0.3	4.2	-

	iii	Semi-Skilled	0.044	0.616	-
11		Masonry Brick Work (AR0603c) : Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	18.4051554464	Cum
	i	Un-Skilled	2.96	54.479260121344	-
	ii	Skilled	1.05	19.32541321872	-
	iii	Highly-Skilled	0.35	6.44180440624	-

12	<p>Masonry Brick Work (AR0603ci) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	29.095512	Cum
i	Un-Skilled	2.96	86.12271552	-
ii	Skilled	1.05	30.5502876	-
iii	Highly-Skilled	0.35	10.1834292	-
13	<p>Plastering (AR1004) : 12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.</p>	-	79.710774	Sqm
i	Un-Skilled	0.12	9.56529288	-

	ii	Skilled	0.14	11.15950836	-
14		Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	142.699008	Sqm
	i	Un-Skilled	0.24	34.24776192	-
	ii	Skilled	0.16	22.83184128	-
15		miscellaneous (ARM031) : Labour for fitting and fixing-departmental shutters excluding cost of fixing and fitting Chaukath - Labour for fitting and fixing-departmental shutters excluding cost of fixing and fitting Chaukath but including mending size of grooves in chaukaths and size of shutters,etc. complete (Doors and Window) and as directed by Engineer-in-Charge.	-	11.705778	Sqm

16	<p>miscellaneous (ARM106) : Labour for fitting and fixing of M.S. Gates as per approved design including cost of all materials complete (Iron works) and as directed by Engineer-in-Charge. - Labour for fitting and fixing of M.S. Gates as per approved design including cost of all materials complete (Iron works) and as directed by Engineer-in-Charge.</p>	-	11.705778	Sqm	
17	<p>Flooring (AR0817bak) : g Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm Plain (Ivory) in wall cladding/ glazed tiles on 12mm thick cement plaster (1:3)(For repair and maintenance) . - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm Plain (Ivory) in wall cladding/ glazed tiles on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles(For repair and maintenance).</p>	-	56.856636	Sqm	
	i	Un-Skilled	0.325	18.4784067	-
	ii	Highly-Skilled	0.325	18.4784067	-

18	Painting (AR0918) : Finishing wall with two coat waterproofing cement paint of approved shade in the inner surface of old work(Inside) - Finishing wall with two coat waterproofing cement paint of approved shade in the inner surface of old work to give an even shade including all costs of labour, Paint and Brushes required for the work, etc. complete and as per direction of Engineer-in-charge. (Inside)	-	68.567	Sqm
i	Un-Skilled	0.032	2.194144	-
ii	Highly-Skilled	0.022	1.508474	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	357.99476799248	462	165393.58281253
1	Skilled	156.84569035459	562	88147.277979282
2	Semi-Skilled	70.170099205713	512	35927.090793325
3	Highly-Skilled	49.00615890624	612	29991.769250619
Total:				319459.72083575