

ESTIMATION DPR							
State	Odisha	District	Sambalpur	Block	Rairakhol	Gram Panchayat	Kadaligarh

Work Code	OD/371/3565/121404/382483/00038127 (Repair & maintenance of Tantagard UP School)
Project Category	Building

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Rairakhol	Proposal Date	-
Date of Commencement	25-03-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance of Primary School Building
Project Sub-Category	Elementary School	Project Type	Repair and Maintenance
Name of Executant	Manas Ranjan Tripathy		

Administrative Approval Details

Approval No.	OD/371/3565/121404/382483/00038127/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/371/3565/121404/382483/00038127/TS
Fund Sanction No.	27871
Fund Sanction Amount (in Rs.)	200000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	Painting (AR0901d) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	258.3	Sqm

	i	Highly-Skilled	0.053763440860215	13.887096774194	-
	ii	Un-Skilled	0.053763440860215	13.887096774194	-
2		Painting (AR0901ci) : Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces(Outer surface) - Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	356.115	Sqm
	i	Highly-Skilled	0.053763440860215	19.145967741935	-
	ii	Un-Skilled	0.053763440860215	19.145967741935	-
3		Painting (AR0922) : Finishing wall two coats with distemper of approved shades on new work (Inside) - Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	258.3	Sqm
	i	Highly-Skilled	0.052	13.4316	-

	ii	Un-Skilled	0.062	16.0146	-
4		<p>Painting (AR0918g) : Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work .(Outside) - Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)</p>	-	356.11	Sqm
	i	Un-Skilled	0.11776344086022	41.936738924731	-
	ii	Highly-Skilled	0.10776344086022	38.375638924731	-
5		<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	3.0375	Cum
	i	Un-Skilled	0.516	1.56735	-

6	Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	0.3375	Cum
i	Un-Skilled	0.1236	0.041715	-
7	Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	2.5319	Cum
i	Skilled	0.18	0.455742	-
ii	Un-Skilled	3.9	9.87441	-

8	Masonry Brick Work (AR0603c) : Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	2.2425	Cum
i	Un-Skilled	2.96	6.6378	-
ii	Skilled	1.05	2.354625	-
iii	Highly-Skilled	0.35	0.784875	-

9	<p>Masonry Brick Work (AR0603ci) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.</p>	-	4.14	Cum
	i Un-Skilled	2.96	12.2544	-
	ii Skilled	1.05	4.347	-
	iii Highly-Skilled	0.35	1.449	-
10	<p>Plastering (AR1014i) : 16mm thick cement Plaster in CM (1:6) over brick work in outside (outside) - 16mm thick cement Plaster in CM (1:6) over brick work in outside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.</p>	-	36	Sqm

	i	Un-Skilled	0.24	8.64	-
	ii	Skilled	0.16	5.76	-
11		Dismantling (AR1612) : Dismantling and removing 2.5 cm. thick artificial stone flooring - Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.	-	32.749	Sqm
	i	Un-Skilled	0.21505376344086	7.0427956989247	-
12		Painting (AR0903i) : Painting two coats of enamel paint in outer surface paint (outer surface) - Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)	-	31.32	Sqm
	i	Highly-Skilled	0.13440860215054	4.2096774193548	-
	ii	Un-Skilled	0.11827956989247	3.7045161290323	-

13	Flooring (AR0802ik) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips(For repair and maintenance). - 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge(For repair and maintenance) .	-	32.749	Sqm
i	Un-Skilled	0.36	11.78964	-
ii	Highly-Skilled	0.13	4.25737	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Highly-Skilled	95.541225860215	612	58471.230226452
1	Un-Skilled	152.53703026882	462	70472.107984194
2	Skilled	12.917367	562	7259.560254
Total:				136202.89846465