

ESTIMATION DPR							
State	Odisha	District	Sundargarh	Block	Nuagaon	Gram Panchayat	Khuntgaon

Work Code	OD/373/3585/121719/384482/00021835 (Provision Of Facility Centre At Khutgaon GP Hqrs)
Project Category	Building

Financial Year	2023-24	Execution Level	PS
Executing Agency	Panchayat Samiti, Nuagaon	Proposal Date	-
Date of Commencement	16-03-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Provision of Facilities at GP Head Quarter
Project Sub-Category	GP Facility Centre	Project Type	New Work
Name of Executant	Srima Subhadarsini Debata		

Administrative Approval Details

Approval No.	OD/373/3585/121719/384482/00021835/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/373/3585/121719/384482/00021835/TS
Fund Sanction No.	11938
Fund Sanction Amount (in Rs.)	1000000

LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<p>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift -</p> <p>Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	29.8512	Cum

	i	Un-Skilled	0.516	15.4032192	-
2		Earth Work (AR0115) : Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	36.63705	Cum
	i	Un-Skilled	0.1236	4.52833938	-
3		Concrete (AR0303) : Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	9.89425	Cum
	i	Skilled	0.18	1.780965	-
	ii	Un-Skilled	3.9	38.587575	-

4	Masonry Brick Work (AR0603c) : Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	11.37228	Cum
i	Un-Skilled	2.96	33.6619488	-
ii	Skilled	1.05	11.940894	-
iii	Highly-Skilled	0.35	3.980298	-

5	Masonry Brick Work (AR0603ci) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	28.94757	Cum
i	Un-Skilled	2.96	85.6848072	-
ii	Skilled	1.05	30.3949485	-
iii	Highly-Skilled	0.35	10.1316495	-

6	R.C.C. Work (AR0404A) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	23.430475	Cum
i	Un-Skilled	1.3333	31.2398523175	-
ii	Skilled	0.1	2.3430475	-
iii	Semi-Skilled	0.0573	1.3425662175	-

7	<p>R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.</p>	-	21	Qntl
i	Un-Skilled	0.8	16.8	-
ii	Highly-Skilled	0.3	6.3	-
iii	Semi-Skilled	0.044	0.924	-
8	<p>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	59.46	Sqm
i	Semi-Skilled	0.05	2.973	-

	ii	Skilled	0.05	2.973	-
9		R.C.C. Work (AR0410e) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm	-	21.11	Sqm
	i	Semi-Skilled	0.16025641025641	3.3830128205128	-
	ii	Skilled	0.16025641025641	3.3830128205128	-
10		R.C.C. Work (AR0410d) : Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm	-	42.76	Sqm
	i	Semi-Skilled	0.6547619047619	27.997619047619	-
	ii	Skilled	0.6547619047619	27.997619047619	-

11	<p>R.C.C. Work (AR0410a) : Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height</p>	-	61.0034	Sqm
i	Semi-Skilled	0.305555555555556	18.6399277777778	-
ii	Skilled	0.305555555555556	18.6399277777778	-
12	<p>Plastering (AR1004) : 12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp. and as per direction of Engineer-in-charge.</p>	-	106.423	Sqm
i	Un-Skilled	0.12	12.77076	-
ii	Skilled	0.14	14.89922	-

13	Plastering (AR1014) : 16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	95.791	Sqm
i	Un-Skilled	0.24	22.98984	-
ii	Skilled	0.16	15.32656	-
14	Plastering (AR1027) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	-	60.7534	Sqm
i	Un-Skilled	0.17	10.328078	-
ii	Skilled	0.14	8.505476	-

15	<p>Concrete (AR0317) : 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips - 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips including hoisting and laying in position compacting and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge. (new work)</p>	-	64.4425	Sqm	
	i	Un-Skilled	0.36	23.1993	-
	ii	Highly-Skilled	0.1	6.44425	-
16	<p>Flooring (AR0817aa) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.</p>	-	3.921	Sqm	

	i	Highly-Skilled	0.325	1.274325	-
	ii	Un-Skilled	0.325	1.274325	-
	iii	Semi-Skilled	0.76	2.97996	-
17		Other Building Items. (AR1901B) : Vitrified Tile 600mmx600mm Plain Ivory - Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)	-	41.564	Sqm
	i	Un-Skilled	0.216	8.977824	-
	ii	Highly-Skilled	0.216	8.977824	-

18	<p>Flooring (AR0817bk) : Fixing Ceramic Tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3)(For repair and maintenance) - Fixing Ceramic Tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles, including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in- charge(For repair and maintenance) .</p>	-	41.4	Sqm
i	Un-Skilled	0.325	13.455	-
ii	Highly-Skilled	0.325	13.455	-

19	<p>Flooring (AR0817a) : Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) - Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in- charge</p>	-	11.615	Sqm	
	i	Highly-Skilled	0.325	3.774875	-
	ii	Un-Skilled	0.325	3.774875	-
	iii	Semi-Skilled	0.76	8.8274	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
0	Un-Skilled	322.6757438975	462	149076.19368064
1	Skilled	138.18467064591	562	77659.784903001
2	Highly-Skilled	54.3382215	612	33254.991558
3	Semi-Skilled	67.06748586341	512	34338.552762066

Total: 294329.52290371