

ESTIMATION DPR							
State	Odisha	District	Bargarh	Block	Jharbandh	Gram Panchayat	Kandadangar

Work Code	OD/347/3318/116508/379899/00042707 (Renovation of Banda Munda Ghuri Munda)
Project Category	Water Body

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Jharbandh	Proposal Date	-
Date of Commencement	-	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance of Capital Assets
Project Sub-Category	Tank	Project Type	Renovation or Rejuvenation
Name of Executant	SAMARENDRA BEHERA		

Administrative Approval Details

Approval No.	OD/347/3318/116508/379899/00042707/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/347/3318/116508/379899/00042707/TS
Fund Sanction No.	26956
Fund Sanction Amount (in Rs.)	387500

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
--------	------------------------	---	---------------------------	------

1	<p>Special items for irrigation works(AR0216) .Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum within an initial lead of 1km from the place of excavation. - Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the the excavated materials away from work site as per the specification and as directed by the Engineer-in-charge within an initial lead of 1km from the place of excavation complete. Per 1 cum.</p>	-	5643	Cum
i)	BRMMR0065 : Add for trimming of slope and bed manually.	1	5643	L.S.
ii)	BRMMR0102 : Cost of mechanical excavation per cum without supervision charge for item AR0216	1	5643	Cum
iii)	BRMMR0104 : ost of transportation of loose earth within the initial lead of 1 km, excluding supervision charges - AR0216	1	5643	Cum

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	BRMMR0065	5643	L.S.	1	5643
2	BRMMR0102	5643	Cum	25.01	141131.43
3	BRMMR0104	5643	Cum	40.49	228485.07

Total: 375259.5