

ESTIMATION DPR							
State	Odisha	District	Mayurbhanj	Block	Saraskana	Gram Panchayat	Umadeipur

Work Code	OD/365/3507/120357/387890/00017424 (Construction of CC road from Kalu Mandal house to Debu Mandal house at Pandhada Mandal Sahi Umadeipur GP)						
Project Category	Road						

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Saraskana	Proposal Date	01-03-2025
Date of Commencement	24-07-2025	Date of Completion	15-10-2025
Scheme Name	Chief Minister Special Assistant	Scheme Component Name	Special Problem Fund (SPF) 16 th Phase
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	GURUVA PURTY		

Administrative Approval Details

Approval No.	OD/365/3507/120357/387890/00017424/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/365/3507/120357/387890/00017424/TS
Fund Sanction No.	2544
Fund Sanction Amount (in Rs.)	600000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	38.9685	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	31.926	Cum
i)	BRM029 : Sand for filling and road blinding	1	31.926	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	41.316	Cum
i)	BRM340 : Cement	2.29	94.61364	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	19.83168	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	39.66336	1 Cum.

4	Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.	-	34.2735	Cum
i)	BRM340 : Cement	3.23	110.703405	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	15.423075	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	30.84615	1 Cum.
5	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	46.95	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.1253565	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	5.9157	1Mtr.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	31.926	1 Cum	531.74	16976.33124
2	BRM340	205.317045	1 Qntl.	650.732	133606.37132694
3	BRM028	35.254755	1 Cum	538.16	18972.6989508
4	BRM044	39.66336	1 Cum.	1466.56	58168.6972416
5	BRM056	30.84615	1 Cum.	1867.93	57618.4489695
6	BRM104	0.1253565	1Cum.	58620.646	7348.479010299
7	BRM092	5.9157	1Mtr.	276.666	1636.6730562
					Total: 294327.69979534