

ESTIMATION DPR							
State	Odisha	District	Kandhamal	Block	Tumudibandh	Gram Panchayat	Belaghar

Work Code	OD/359/3433/119010/417077/00049620 (CONST. OF CC ROAD FROM RANGAPARU SCHOOL TO GIRISAKSA VILLAGE)
Project Category	Road

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Tumudibandh	Proposal Date	-
Date of Commencement	21-03-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	MAINTENANCE OF ROADS AND BRIDGES
Project Sub-Category	CC Road	Project Type	New Work
Name of Executant	Pranya Kumar Mishra		

Administrative Approval Details

Approval No.	OD/359/3433/119010/417077/00049620/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/359/3433/119010/417077/00049620/TS
Fund Sanction No.	32004
Fund Sanction Amount (in Rs.)	500000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	21.786238	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	11.39963576	Cum
i)	BRM029 : Sand for filling and road blinding	1	11.39963576	1 Cum
3	Concrete (AR0303a) :.Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal - Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	57.97935592	Cum
i)	BRM340 : Cement	2.29	132.7727250568	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	27.8300908416	1 Cum
iii)	BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	55.6601816832	1 Cum.

4	<p>Concrete (AR0307) :.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	10.7462256	Cum
i)	BRM340 : Cement	3.23	34.710308688	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	4.83580152	1 Cum
iii)	BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	9.67160304	1 Cum.
5	<p>R.C.C. Work (AR0404A) :.Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)</p>	-	4.24752	Cum
i)	BRM340 : Cement	3.4733	14.752911216	1 Qntl.

ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	1.911384	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1.5291072	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	2.2936608	1 Cum.
6	R.C.C. Work (AR0409) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	4.25	Qntl
i)	BRM162 : Binding Wire.	0.8	3.4	1 Kg.
ii)	BRM341 : Steel	1.05	4.4625	1 Qntl.

7	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	94.76106	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.2530120302	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	11.93989356	1Mtr.
8	R.C.C. Work (AR0410a) :.Centring & Shuttering for R.C.C. floor and roof slabs, landings,balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height	-	13.00642	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.6222222222222222	8.09288355555556	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0050222222222222	0.065321131555556	1Cum.

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	11.39963576	1 Cum	671.51	7654.9694091976
2	BRM340	182.2359449608	1 Qntl.	632.632	115288.29033244
3	BRM028	34.5772763616	1 Cum	743.49	25707.859202086

4	BRM045	55.6601816832	1 Cum.	1128.47	62810.845224041
5	BRM056	9.67160304	1 Cum.	1998.13	19325.120182315
6	BRM060	1.5291072	1 Cum.	2020.18	3089.071783296
7	BRM052	2.2936608	1 Cum.	1983.8	4550.16429504
8	BRM162	3.4	1 Kg.	90.1	306.34
9	BRM341	4.4625	1 Qntl.	7133.412	31832.85105
10	BRM104	0.31833316175556	1Cum.	58573.086	18645.75566016
11	BRM092	11.93989356	1Mtr.	229.106	2735.5012539574
12	BRM084	8.0928835555556	1Mtr	250.166	2024.5643075591
Total: 293971.33270009					