

ESTIMATION DPR							
State	Odisha	District	Kandhamal	Block	Phiringia	Gram Panchayat	Balandapada

Work Code	OD/359/3429/118957/415124/00070643 (Construction of GP Facility center at Balandapada GP)						
Project Category	Building						

Financial Year	2022-23	Execution Level	PS
Executing Agency	Panchayat Samiti, Phiringia	Proposal Date	-
Date of Commencement	07-01-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Provision of Facilities at GP Head Quarter
Project Sub-Category	GP Facility Centre	Project Type	New Work
Name of Executant	BIBHUDANANDA BISWAL		

Administrative Approval Details

Approval No.	OD/359/3429/118957/415124/00070643/AS
--------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/359/3429/118957/415124/00070643/TS
Fund Sanction No.	22566
Fund Sanction Amount (in Rs.)	1000000

MATERIAL STATEMENT

Sl.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift - Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	35.11849536	Cum

2	Earth Work (AR0115) :.Filling foundation and plinth with sand well watered and rammed - Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.	-	5.55858784	Cum
i)	BRM029 : Sand for filling and road blinding	1	5.55858784	1 Cum
3	Concrete (AR0303) :.Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal - Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.	-	20.338631845642	Cum
i)	BRM340 : Cement	2.29	46.57546692652	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.48	9.7625432859082	1 Cum
iii)	BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	19.525086571816	1 Cum.

4	R.C.C. Work (AR0404A) ∴ Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips - Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)	-	18.954430546083	Cum
i)	BRM340 : Cement	3.4733	65.83442361571	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.45	8.5294937457373	1 Cum
iii)	BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	6.8235949965899	1 Cum.
iv)	BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	10.235392494885	1 Cum.

5	R.C.C. Work (AR0409) :.Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position - Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.	-	17.61	Qntl
i)	BRM162 : Binding Wire.	0.8	14.088	1 Kg.
ii)	BRM341 : Steel	1.05	18.4905	1 Qntl.
6	R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	51.25179801	Sqm
i)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.1368423006867	1Cum.
ii)	BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.126	6.45772654926	1Mtr.

7	R.C.C. Work (AR0410e) :.Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm	-	11.93710647	Sqm
i)	BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.26923076923077	3.2138363573077	1Mtr.
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0052948717948718	0.063205448360385	1Cum.
8	R.C.C. Work (AR0410d) :.Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm	-	54.1162576284	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.55238095238095	29.892789928069	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0051904761904762	0.28088914673789	1Cum.

9	R.C.C. Work (AR0410a) :.Centring & Shuttering for R.C.C. floor and roof slabs, landings,balconies, projecting sun shades and chajjas - Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height	-	56.0619530283	Sqm
i)	BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.622222222222222	34.882992995387	1Mtr
ii)	BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0050222222222222	0.28155558631991	1Cum.
10	Masonry Brick Work (AR0603b) :.Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	5.27599537896	Cum
i)	BRM340 : Cement	0.672	3.5454688946611	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.28	1.4772787061088	1 Cum

iii)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm$ 2 %	350	1846.598382636	1000 Nos
11	Masonry Brick Work (AR0603bi) : Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure - Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance $\pm$ 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.	-	20.949936708	Cum
i)	BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	20.949936708	1 Cum
ii)	BRM340 : Cement	0.672	14.078357467776	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.28	5.86598227824	1 Cum
iv)	BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm$ 2 %	350	7332.4778478	1000 Nos

12	Plastering (AR1004) :.12mm thick cement plaster (1:6) over Brick work in inside - 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.	-	76.2269115	Sqm
i)	BRM340 : Cement	0.0358	2.7289234317	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.015	1.1434036725	1 Cum
13	Plastering (AR1014) :.16mm thick cement Plaster in CM (1:6) over brick work in inside. - 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.	-	126.22916416	Sqm
i)	BRM340 : Cement	0.043	5.42785405888	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.018	2.27212495488	1 Cum

14	Flooring (AR0817aa) :.Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) - Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.	-	35.9160954134	Sqm
i)	BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B Ia) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	1	35.9160954134	1 Sqm.
ii)	BRMMR0027 : Wax Polish	1	35.9160954134	1 Sqm
iii)	BRM340 : Cement	0.1375	4.9384631193425	1 Qntl.
iv)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.538741431201	1 Cum

15	Flooring (AR0817b) :.Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) - Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.	-	24.39261168	Sqm
i)	BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	1	24.39261168	1 Sqm.
ii)	BRM340 : Cement	0.1375	3.353984106	1 Qntl.
iii)	BRM028 : Screened and washed sharp sand for mortar	0.015	0.3658891752	1 Cum
16	Painting(AR0901d) :.Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface) - Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	154.95941691	Sqm

i)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.084	13.01659102044	1 Ltr
17	Painting(AR0901di) :.Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces(outer surface) - Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.	-	78.781744	Sqm
i)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	7.1157704258065	1 Ltr
18	Painting(AR0920b) :.Finishing wall surface with two coats with plastic emulsion paint of approved shades above one coat waterbound Primer on new work (Inside) - Finishing wall surface with two coats with plastic emulsion paint of approved shades above one coat waterbound Primer on new work to give an even shade including all costs of labor, Paint, Primer, Brushes and putty required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)	-	238.87683875	Sqm
i)	BRM140 : Plastic Emulsion paint	0.125	29.85960484375	1 Litre
ii)	BRM253 : Wall cement primer (I.S.I.) Water bound	0.084	20.065654455	1 Ltr

19	Plastering (AR1026) :.6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces (inside) - 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.	-	50.93406975	Sqm
i)	BRM340 : Cement	0.0271	1.380313290225	1 Qntl.
ii)	BRM028 : Screened and washed sharp sand for mortar	0.0075	0.382005523125	1 Cum
20	Painting(AR0903b) :.Painting two coats of enamel paint with a coat of red oxide primer over iron surface - Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.	-	30.12379775	Sqm
i)	BRM137 : Red oxide Primer	0.054	1.6266850785	1 Litre
ii)	BRM141 : Enamel paint	0.125	3.76547471875	1 Litre
21	Other Building Items. (AR1902) :.cement based wall putty (water based) - Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc.co mplete. and as per the direction of Engineer in Charge.	-	133.38826934	Sqm

i)	BRMMR0038 : Cement based putty	0.8	106.710615472	kg
----	--------------------------------	-----	---------------	----

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRM029	5.55858784	1 Cum	411.11	2285.1910469024
2	BRM340	147.86325491081	1 Qntl.	656.412	97059.214882518
3	BRM028	30.3374627729	1 Cum	938.79	28480.506676571
4	BRM044	19.525086571816	1 Cum.	1857.16	36261.209777714
5	BRM060	6.8235949965899	1 Cum.	2280.58	15561.754277323
6	BRM052	10.235392494885	1 Cum.	2244.2	22970.267837021
7	BRM162	14.088	1 Kg.	90.1	1269.3288
8	BRM341	18.4905	1 Qntl.	7157.192	132340.058676
9	BRM104	0.76249248210488	1Cum.	58620.646	44697.801871131
10	BRM092	6.45772654926	1Mtr.	276.666	1786.6333734776
11	BRM094	3.2138363573077	1Mtr.	287.666	924.51144956127
12	BRM084	64.775782923455	1Mtr	297.726	19285.434746669
13	BRM005	9179.076230436	1000 Nos	7.28935	66909.499320329
14	BRMMR0025	20.949936708	1 Cum	33	691.347911364
15	BRM131	35.9160954134	1 Sqm.	675.4086121	24258.040155216
16	BRMMR0027	35.9160954134	1 Sqm	8.5	305.2868110139
17	BRM129	24.39261168	1 Sqm.	429.5286121	10477.324640405
18	BRM253	40.198015901246	1 Ltr	159.81292	6424.1622993846
19	BRM140	29.85960484375	1 Litre	250.12292	7468.5715535649
20	BRM137	1.6266850785	1 Litre	143.48292	233.40152498361
21	BRM141	3.76547471875	1 Litre	206.12292	776.15064421493
22	BRMMR0038	106.710615472	kg	30	3201.31846416

Total: 523667.01673952