

ESTIMATION DPR							
State	Odisha	District	Balangir	Block	Puintala	Gram Panchayat	Sauntpur

Work Code	OD/345/3294/115982/420061/00037883 (IMPROVEMENT OF JADAMUNDA AT UMURIA)
Project Category	Water Body

Financial Year	2025-26	Execution Level	PS
Executing Agency	Panchayat Samiti, Puintala	Proposal Date	-
Date of Commencement	10-03-2026	Date of Completion	-
Scheme Name	5th SFC Grant in Aid	Scheme Component Name	Maintenance of Capital Assets
Project Sub-Category	Tank	Project Type	Upgradation or Improvement
Name of Executant	Nirlipta Samal		

Administrative Approval Details

Approval No.	OD/345/3294/115982/420061/00037883/AS
---------------------	---------------------------------------

Technical Sanction Details

Technical Sanction No.	OD/345/3294/115982/420061/00037883/TS
Fund Sanction No.	33742
Fund Sanction Amount (in Rs.)	400000

MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	Earth Work (AR0122Bi) :.Earthwork in ordinary soil within 5 Km. mechanical carriages and spreading in filling area/road berm within initial lead and lift - Earthwork in ordinary soil within 5 Km. mechanical carriages and spreading in filling area/road berm within initial lead and lift including dressing and leveling the bed, etc. as per direction of Engineer-in-Charge.	-	1094.3522904	Cum

i)	BRMM402 : Loading into trucks and unloading from trucks within 50 Meter lead (2/3 of rate is consider for loading).	-0.6666	-729.49523678064	1 Cum
ii)	BRMM401 : Conveyance of material by 10 ton trucks within 5 KM including loading and unloading	1	1094.3522904	1 Cum
2	Special items for irrigation works(AR0216) :.Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum within an initial lead of 1km from the place of excavation. - Excavation, loading, unloading, and carriage by mechanical means of all kinds of soil, including stoney earth, gravel, and moorum etc interspread with boulders upto 1/2 cum size with all lifts and delifts including trimming of slopes and bed to design section and depositing the the excavated materials away from work site as per the specification and as directed by the Engineer-in-charge within an initial lead of 1km from the place of excavation complete. Per 1 cum.	-	788.5662464	Cum
i)	BRMMR0065 : Add for trimming of slope and bed manually.	1	788.5662464	L.S.
ii)	BRMMR0102 : Cost of mechanical excavation per cum without supervision charge for item AR0216	1	788.5662464	Cum
iii)	BRMMR0104 : ost of transportation of loose earth within the initial lead of 1 km, excluding supervision charges - AR0216	1	788.5662464	Cum

Sl.No.	Material Name	Qty	Unit	Rate	Amount
1	BRMM402	-729.49523678064	1 Cum	175.38	-127938.87462659
2	BRMM401	1094.3522904	1 Cum	276.01	302052.1756733
3	BRMMR0065	788.5662464	L.S.	1	788.5662464
4	BRMMR0102	788.5662464	Cum	25.01	19722.041822464
5	BRMMR0104	788.5662464	Cum	40.49	31929.047316736
					Total: 226552.95643232